

Volume 3
Issue 3

RISC USER


JANUARY/FEBRUARY 1990
Price £1.60

Filetype Setter

System Fonts

SCSI Interfaces

Sound Module Generator



Outline Fonts

The magazine and
support group
exclusively for users
of the Archimedes



CONTENTS

FEATURES

News	4
System Fonts	23
Into the ARC: Desktop Publishing with Draw	25
Assembler Workshop: The Role of Register R15	37
Mastering the Wimp (Part 5): Responding to Redraw Requests	49
Under the Lid (Part 4)	53
Hints & Tips	60
Postbag	63
Technical Queries	65

UTILITIES AND APPLICATIONS

Setting Filetypes	9
Coloured Text Panels	15
A Voice Module Generator	20
A Check Save Module	44

REVIEWS

SCSI Interfaces: An Alternative Approach to Hard Discs	7
Jigsaw - A Real Puzzle	11
Outline Fonts	13
Clares' Artisan 2	29
Using Laser Printers: The Panasonic KX-P4450	31
Probing Pascal	41
Hyperbook	46

RISC USER

RISC User is published by BEEBUG Ltd.

Co-Editors:

Dr Lee Calcraft, Mike Williams

Assistant Editor: Kristina Lucas

Technical Editor: Alan Wrigley

Technical Assistant: Glyn Clements

Production Assistant: Sheila Stoneman

Advertising: Sarah Shrive

All rights reserved. No part of this publication may be reproduced without prior written permission of the Publisher.

The Publisher cannot accept any responsibility whatsoever for errors in articles, programs, or advertisements published. The opinions expressed on the pages of this journal are those of the authors and do not necessarily represent those of the Publisher, BEEBUG Limited.

BEEBUG Ltd © 1990

BEEBUG, 117 Hatfield Road, St. Albans, Herts AL1 4JS.

Tel: St. Albans (0727) 40303.

Fax: (0727) 60263



Welcome to the first issue of RISC User for the nineteen nineties. As you will have seen, unless you only recently joined RISC User, we introduced a new look for RISC User from the start of volume 3, which we hope will make the magazine more attractive and easier to read.

However, the value of RISC User, as with any magazine, lies in its content rather than its presentation, although poor style will, of course, fail to do justice to good content, and indeed may detract from it. As many readers will know, we carried out an extensive reader survey in the middle of last year, and the content of RISC User has undergone a number of changes as a result.

The magazine has grown significantly in size over the last 12 months, allowing us not only to include more editorial material than before, but also to cater better for specialist interests as well. However, RISC User caters for a wide and varied readership, so do remember this if we do not always devote as much space as you might wish to your pet interest.

A reader survey, however useful and comprehensive, can only attempt to convey the opinions of readers at one point in time. Acorn, and other suppliers, will certainly not stand still, and we can no doubt expect some exciting developments during this year. The mix of Archimedes owners likewise does not remain the same. Already it is becoming clear that many early Archimedes purchasers were previously BBC owners; more recently the success of the Archimedes range has attracted a wider range of new purchasers.

This has been very obvious to us in conversations which we have had at our

two open days, where we have very much enjoyed the opportunity of meeting and talking both with existing readers and potential readers for the future.

If RISC User is to continue to satisfy the needs of Archimedes owners, then we still very much need to listen to your views, not only on the magazine, its presentation and content, but on any matters related to the Archimedes. We hope that in the forthcoming months you will continue to let us know what you think, by letter or by phone. Of course, if you can contribute in other ways, such as questions for our Technical Queries page, hints & tips, programs, articles or anything else related to the Archimedes and its use, then we would be equally delighted to hear from you.

NEW STAFF

Back in the October issue (Volume 2 issue 10) we referred to the departure of our then Technical Editor, David Spencer, to a new position in charge of hardware development within BEEBUG. We are now delighted to welcome Alan Wrigley to the team as our new Technical Editor.

MISSING PAGES

As a final footnote, it appears that the Programmer's Reference Manual is missing pages 130, 132 and 134 (and three pages are duplicated). Acorn says that the omission will be rectified in future editions, but has kindly made the missing information available in machine readable form for the monthly magazine disc (see inside back cover). We can also supply a photocopy of the missing pages in return for 50p (to cover costs) and an A5 or larger SAE. Please mark your request PRM Pages.

• News • News • News • News •

BEEBUG/RISC USER SUMMER COMPETITION

The winner of our Summer Competition, Paul Warren, and his wife visited BEEBUG before Christmas when Paul was able to collect his prize of an A3000 colour system donated by Acorn. Paul, who has an issue 3 model B BBC micro, was highly delighted at his good fortune, and was looking forward to an increased interest in home computing with his new system. Paul claims no great mathematical ability, but says that once he started on the competition, he just became 'hooked'. Our congratulations to Paul.

ACORN NEWS

As well as being distributed through Dixons' 'flagship' high street stores, the A3000 is now available through ten of the leading stores in the John Lewis Partnership, and through four Adlers stores. This should further widen the appeal of the A3000 with the general public.

A special discount offer has been announced by Acorn on complete R140 (UNIX) systems. For £2999 (plus VAT) Acorn is bundling an R140 RISC-based workstation with hard disc and Ethernet networking, plus a choice of either PC emulator software and 14" Taxan colour monitor, or a 19" Taxan monochrome monitor.


For more information on Acorn products contact Acorn Computers Ltd. at Fulbourn Road, Cambridge CB1 4JN, tel. (0223) 245200.

NEW RELEASES FROM SILICON VISION

Silicon Vision has announced RISC OS versions of many of its software products: SolidCAD Design System (£99.95), Realtime Solids Modeller (£149.95), with upgrades costing £50.00 for existing users (prices include VAT).

A new product in the CAD marketplace is SolidTools, a fully integrated environment for 3D CAD, photo-realistic rendering, interactive animation with high-resolution hard copy to printers and plotters. This combines the features of previously separate products, SolidCAD, SolidsRender and FilmMaker. The price of SolidTools has been set at £275 (inc. VAT).

For PCB design, Silicon Vision has introduced GerberPlot to complement its existing Arc-PCB and Arc-PCB Professional products. The new software allows industry standard gerber plot files to be produced, which may be sent to photoplotter bureaux for high quality PCB artwork. GerberPlot costs £125 (again inc. VAT).



Silicon Vision's RISC OS version of Solid CAD

For business users Silicon Vision has announced a RISC OS version of its business software, Presentation System (£49.95), and new office automation products: DataVision (£99.95), Financial Accountant (£175.00), and ShareHolder (£99.95). The complete suite of programs is also available as a single system called OfficeTools and costing £295.00 (all prices inclusive of VAT).

Silicon Vision may be contacted at Signal House, Lyon Road, Harrow, Middx HA1 2AG, tel. 01-422 2274.(*).

DIGITISER FROM PINEAPPLE

The latest digitiser for the Archimedes comes from Pineapple Software, well known for its CAD and PCB Design software. The new device is a full colour Video Digitiser/Frame Grabber at just £327.75 inc. VAT. An extended (16 bit storage as opposed to 12 bit) will be available for 362.25 (inc. VAT). Pineapple claims that the low price in no way indicates poor design or quality. The PAL decoder at the heart of the device converts a coded signal from a VCR, TV tuner or camera etc. into the RGB components, and is a high quality design with both luminance and chrominance delay lines to ensure the highest quality decoding.

The new device is expected to be available shortly, and orders are already being taken. Pineapple Software is at 39 Brownlea Gardens, Seven Kings, Ilford, Essex IG3 9NL, tel. 01-599 1476.

NEW ARCHIMEDES ROM FROM ACORN

Acorn is believed to be working on a new 1Mbyte version of the RISC OS chip set (currently 0.5Mbytes) which will incorporate applications such as Draw, Edit, Paint and possibly the Basic Editor, presently supplied on the Applications Discs, and even cached fonts and C libraries. What is more, these applications then run from the ROM, leaving many hundreds of K of RAM free. Users of 1Mbyte machines in particular will then find it much easier to use these applications, particularly when multi-tasking, and being ROM rather than disc based, will be immediately available at all times. Unfortunately, the new ROM is only likely to work with the 400/1 series (and A3000).

Availability is some months away, but we believe that Acorn will be offering the new chip set to existing owners as an upgrade.

ALL ARMS

Another source of ARM3 upgrades for the Archimedes has become available. Gnome Computers of Cambridge, better known perhaps for its range of Transputer products for the Archimedes, has released an ARM3 board at £569.25 inc. VAT, undercutting the ARM3 upgrade currently offered by Aleph One (see review in RISC User Volume 2 Issue 10).

Gnome has also released a 4Mbyte to 8Mbyte upgrade for the 440/1 at £1092.50 inc. VAT. This will also benefit the R140 UNIX workstation running X Windows. For more details contact Gnome Computers at 16 Histon Road, Cambridge CB4 3LE, tel. (0223) 461520.

RISC USER READERS IMPRESS ACORN

In addition to BEEBUG's own competition (see above) RISC User distributed a questionnaire from Acorn last year to help Acorn identify particularly interesting and significant applications involving the Archimedes. Acorn offered an Archimedes 410 colour system for the most interesting entry, and £300 worth of software in a prize draw.

In fact, Acorn was so impressed with the standard of entries from RISC User readers that it decided to award two 410 colour systems as prizes. The fortunate winners are Mark Shacklady with an impressive process control application and Alan Brian with a CAD and process plant display and control application. Both have been invited to BEEBUG this month to receive their prizes from Acorn. The winner of the prize draw was Mr. Delaney of Stalmine, near Blackpool, who has already received £300 worth of vouchers to be exchanged for the software of his choice.

PRM REPRINTED

It is now known that Acorn terminated the initial print run of the Programmer's Reference Manual after just 1200 had been printed because of poor reproduction quality. We understand that the manuals have been re-originated to a higher standard, and that the new copies were printed just too late to be dispatched before Christmas. Acorn also took the opportunity to include three pages, previously missing (see this month's editorial) and to make a few other minor corrections. Acorn details are given above. (*)

SCHOOL IS FUN

Database Educational Software has announced that its best selling educational package Fun School 2 (with 60,000 units already sold) is to be released for the Archimedes, and in this format offers superior sound and graphics to any other version. Fun School 2 is available in three versions, one for the under sixes, one for six to eight year olds, and a third for the over eights.

Fun School 2 combines entertainment and education to develop skills in numeracy, literacy and concentration, and all now in a wholly Archimedes environment.

For more information on Fun School 2 contact Database Educational Software at Europa House, Adlington Park, Adlington, Macclesfield SK10 4NP, or tel. (0625) 878888.

All products mentioned which are marked with a '*' are available direct through BEEBUG Retail (see Retail Catalogue). **RU**

ARE YOU GOOD ENOUGH?

As the leaders in software for the Archimedes range of computers, CLARES MICRO SUPPLIES are looking to extend our range even further. We are looking for people who are as excited by the Archimedes as we are.

If you have written any programs, completed or not, then we would like to hear from you.

If you have any ideas for programs and have the ability to execute the ideas then we want to hear from you.

If you have the ability to program the Archimedes but not the ideas to program then we want to hear from you.

Programs can be written in any language as long as they perform their stated task. Many of our programs contain large chunks of BASIC with ARM code in the areas that it is needed. BASIC on the Archimedes is a very powerful language and we do not attach any snob value to its use. If your program does what is meant to do then that's all we are interested in. Why not join the top team on the Archimedes. You get the support of our in-house team, privileged access through us to Acorn and invitations to our informal programmers seminars.

The most important point is that you will be earning top royalty rates of if you prefer we will purchase your program outright.

Please write, in confidence, to Mr. D. Clare at:

**Clares Micro Supplies,
98 Middlewich Road,
Northwich,
CHESHIRE CW9 7DA**

If you have a program either complete or in development then please enclose a copy for our evaluation.

To protect yourself we advise that you lodge a copy of the program with your bank or solicitor BEFORE you send us a copy. You can then prove that your program pre-dates anything that we have.

Act today and become part of the leading software team producing software for the worlds fastest micro.

SCSI Interfaces

- an alternative approach to hard discs

by Mike Williams

More observant readers may well have noticed references in RISC User and other magazines to the term SCSI, particularly in connection with larger capacity hard disc drives. In this report, it is our intention to explain what SCSI is, the significance it has for Archimedes owners, and to look at the SCSI products currently available from two suppliers, Lingenuity and Oak Computers.

INTRODUCING SCSI

SCSI (Small Computer Systems Interface) is a high speed industry-standard interface which allows as many as 7 (possibly different) devices to be connected to a computer through the one interface. Each SCSI device has a unique identity by which it can be recognised, and several SCSI devices are simply daisy-chained together, each device having a SCSI 'input' and a SCSI 'output'.

The SCSI standard is not specific to the Archimedes, and has quite a long history of use, particularly with the Apple Macintosh. Typical devices which might be connected to a SCSI interface include Winchester hard disc drives, tape streamers, CD ROM units and other devices needing high speed throughput.

A SCSI interface uses an eight bit data bus to transfer data to the device connected to it, with a maximum transfer rate of 2Mbytes/sec. In practice, SCSI devices often operate at lower rates, typically some 650Kbytes/sec for a hard disc drive, for example. A further factor is the speed at which the host system can transmit or accept data to or from the SCSI interface.

SCSI AND THE ARCHIMEDES

A SCSI interface fitted to an Archimedes (and that includes the A3000) allows a variety of high speed, high capacity devices to be connected. At present, the devices available are exclusively hard disc drives, although both Lingenuity and Oak say they will have other devices available shortly. In this report we are concerned only with hard disc drives.

For the Archimedes range, a SCSI interface allows a higher capacity drive to be used than is otherwise possible. The Archimedes normally uses a standard ST506 controller for hard disc drives. This permits a maximum capacity of 47Mbytes per drive. SCSI allows hard disc drives of up to 512Mbytes capacity each.

SCSI hard discs have an inherent speed advantage over ST506 drives, but in practice the improvements depend on the drive being used (and the screen mode in use - see later). A worst case comparison still offers a two times improvement, while at best SCSI drives may be nearly 40 times faster than those using the ST506 controller.

SCSI drives do not use the ADFS but an on-board SCSIIFS. This is functionally identical (in both Lingenuity and Oak versions) to the ADFS. A further point of difference (and debate) concerns the width of the data bus connecting the SCSI interface to the Archimedes. The Lingenuity SCSI interface uses an 8 bit data bus, while that from Oak doubles up the bytes and uses one 16 bits wide. The Oak interface can therefore transfer twice as much data on each memory access, and is thus intrinsically faster, but again the speed of the SCSI device may be the more limiting factor.

This point also relates to the screen mode in use when a transfer takes place. As higher resolution modes take more memory, they also take longer for screen refreshes, reducing the time for other data transfers. In mode 21 for example, the ability of the Oak interface to send 16 bits at a time starts to have a major beneficial effect on timing relative to the Lingenuity board. In modes such as 12 and 15 the difference is much less marked.

THE INTERFACES REVIEWED

Both Lingenuity and Oak only supplied Archimedes (not A3000) interfaces for review purposes. Both interface boards use the same

(though non standard) connector for linking to a hard drive. This is fine if you buy your drive at the same time, but check if you are obtaining your drive separately. Both interfaces are made to a high standard and feature the same controller chip. The Oak board has more components as befits its use of a 16 bit data bus.

In practice, installing an interface and connecting it to a hard drive is quite straightforward, though care is needed. Once an interface has been fitted to the Archimedes, a 50 way ribbon cable then connects interface to drive. Disc drives may be internal or external, but the latter incorporate a separate power supply and are hence more expensive. Internal drives involve slightly more work in the fitting. Both Lingenuity and Oak supplied external drives for testing.

As far as the A3000 is concerned, the policies of Lingenuity and Oak differ. Oak supply the same SCSI interface mounted in a metal case which is attached to the connector at the left rear of the A3000. Lingenuity supplies a different SCSI card which can be mounted internally, with the SCSI connector flush with the rear of the machine, a generally neater solution. The A3000 has no room for an internal hard disc, and so an external unit must be used with both interfaces.

The Oak system is supplied ready configured, so once installed and switched on, the hard disc icon immediately appears on the icon bar. With Lingenuity's interfaces, the system must first be configured before the SCSI icon appears, a straightforward task which is clearly described in the documentation.

TIMING

A number of typical timings are shown in table 1. The main difficulty here is in comparing like with like. In addition, timings are not constant from any one test even when averaged out. The specific transfer rate of the drive model selected also has an affect. The general impression from our own tests, and from figures supplied by Lingenuity and Oak, is that the Oak interface is faster. However, all SCSI drives are fast compared with an

ST506 hard drive, and like greased lightning compared with a floppy disc.

Drive	Capacity	Data transfer rate (Kbytes/sec)		
		Mode 0	Mode 15	Mode 21
Acorn ST506	20Mb	280	271	16
Oak SCSI	20Mb	607	536	55
Oak SCSI	45Mb	659	659	55
Oak SCSI	70Mb	824	820	511
Lin. SCSI	100Mb	689	487	—
Oak SCSI	170Mb	1255	1147	672

Table 1. Comparative transfer rates

PRICES

The interfaces are available from both Lingenuity and Oak separately, or in complete packages with appropriate drives. Some typical prices (all including VAT) are shown in table 2 (all include interface). Note that Lingenuity's A3000 SCSI interface is £50 less than that for the Archimedes, and thus all Lingenuity external hard discs (inc. SCSI interface) should be similarly cheaper for the A3000.

	Lin.	Oak
Archimedes SCSI interface	£228.85	£228.85
A3000 SCSI interface	£171.35	£228.85
Archimedes 20Mb SCSI (Int.)	£431.25	£448.50
A3000 20Mb SCSI (Ext.)	£546.25	£626.75
Archimedes 45Mb (Int.)	£573.85	£586.50
Archimedes 45Mb (Ext.)	£677.35	£764.75
Archimedes 100Mb (Ext.)	£1068.35	—
Archimedes 170Mb (Ext.)	—	£2144.75

Table 2. Typical SCSI prices (inc. VAT)

CONCLUSIONS

There are many factors to consider when selecting a SCSI drive and interface. If you compare prices for similar capacity SCSI drives from different sources, do check the specifications of the drives themselves. At the end of the day you must decide what features are important to you and then make a final decision. For A3000 owners, a SCSI hard disc upgrade may prove cheaper than any other alternative, and should be considered as a serious option. A last point - disc drive specifications are always liable to change as companies like Lingenuity and Oak choose different sources or models, so make sure you have the latest information. RU

Setting Filetypes

A utility by Mike Ironmonger

The concept of *filetype* is very important within the RISC OS environment, and is the means by which, for example, RISC OS knows what to do with a file when you double click on its icon (e.g. run a Basic program, or load a sprite file into Paint, and so on). However, setting filetype is not easy, until now that is.

The utility listed here gives you full control over filetypes from the Desktop. Once installed on the icon bar, dragging any file to the icon bar icon reads that file's type and places the corresponding 'type' icon on the icon bar as well. Once a filetype has been installed on the icon bar, dragging any file to that icon will change its filetype accordingly.

Alternatively, if you click with the menu button on the application's icon on the icon bar, you can either *quit* from the application (and it disappears from the icon bar), or you can type in the name or hex code for any filetype of your choosing, and the application will create a corresponding filetype icon on the icon bar. If you specify a filetype by a value which is unknown, the application creates an icon which visually incorporates this value.

If you click with the menu button on any installed filetype icon, you will be shown the corresponding filetype name (if known) or value, and you may also choose to remove that filetype icon from the icon bar. The processes involved take much longer to describe than to perform, and a little practice should quickly make everything quite clear.

SETTING UP THE APPLICATION

You will need to create an application directory called !SetType. The easiest way to do this is to use the *Application shell Generator* published last month (Volume 3 Issue 2) which does most of the work for you. Once created, you can open the

application's directory by double clicking on its icon while holding down the Shift key. You will need to type in the program listing given with this article and save it in the application directory as !RunImage.

If you are not using the Application Shell Generator, the !Run file required in the application directory should read as follows:

```
Wimpslot -min 16K -max 16K
Run <Obey$Dir>.!RunImage
```

```
10 REM                >!RunImage
20 REM Program      File type setter
30 REM Version      A 3.10
40 REM Author       Mike Ironmonger
50 REM RISC User    Jan/Feb 1990
60 REM Program      Subject to copyright
70 :
80 PROCinitialise
90 ON ERROR PROCerror(ERR,REPORT$)
100 :
110 REPEAT
120 SYS "Wimp_Poll",681833,block% TO A
%
130 CASE A% OF
140 WHEN 6 : PROCcreate_menu(!block%,b
lock%!!16)
150 WHEN 9 : PROCmenu_select(!block%)
160 WHEN 17,18 : PROCreceive(block%!!16
)
170 ENDCASE
180 UNTIL quit%
190 SYS "Wimp_CloseDown"
200 END
210 :
220 DEF PROCmenu_select(S%)
230 I%=FNwhich_icon(menu_icon%)
240 CASE I% OF
250 WHEN 0 :
260 CASE S% OF
270 WHEN 0 : SYS "OS_FSControl",31,b_t
ype% TO ,,T%:PROCnew_type(T%)
280 WHEN 1 : quit%=TRUE
290 ENDCASE
300 OTHERWISE : PROCquit(I%)
310 ENDCASE
320 ENDPROC
330 :
340 DEF PROCreceive(M%)
350 CASE M% OF
360 WHEN 0 : quit%=TRUE
```

```

370 WHEN 3 : PROCdragged_on(FNwhich_ic
on(block%!24))
380 ENDCASE
390 ENDPROC
400 :
410 DEF PROCquit(I%)
420 !block%=-1:block%!4=menu_icon%
430 SYS "Wimp_DeleteIcon",block%
440 icon%(I%)=-1
450 ENDPROC
460 :
470 DEF PROCdragged_on(I%)
480 block%!12=block%!8:block%!16=4
490 SYS "Wimp_SendMessage",17,block%,b
lock%!4
500 CASE I% OF
510 WHEN 0 : PROCnew_type(block%!40)
520 OTHERWISE SYS "OS_File",&12,block%
+44,type%(I%)
530 ENDCASE
540 ENDPROC
550 :
560 DEF PROCnew_type(T%)
570 IF T%>&FFF ERROR 1,"That object ha
s no file type."
580 I%=FNwhich_icon(-1)
590 IF icon%(I%)<0 ERROR 1,"Can't ha
ndle any more file types."
600 SYS "OS_ConvertHex4",T%,block%,5
610 type%=MID$(block%,2,3)
620 spr$="file."+type$
630 SYS "XWimp_SpriteOp",24,,spr$ TO ;
F%
640 IF (F%AND1)=1 PROCcreate_sprite(sp
r$,type$)
650 type%(I%)=T%
660 PROCcreate_icon(I%,spr$)
670 ENDPROC
680 :
690 DEF PROCcreate_sprite(spr$,type$)
700 SYS "Wimp_BaseOfSprites" TO ,spr%
710 SYS "OS_Module",13,,spr%,180 TO , ,
newspr%
720 !newspr%+=180
730 SYS "OS_Module",18,"WindowManager"
TO , , ,wspace%
740 wspace%!540=newspr%
750 SYS "OS_SpriteOp",&10F,newspr%,spr
$,0,34,17,0
760 SYS "OS_SpriteOp",&13C,newspr%,spr
$ TO R0,R1,R2,R3
770 GCOL7:RECTANGLE 0,0,64,64
780 RECTANGLE 2,0,64,64
790 VDUS:MOVE 10,44:PRINTtype$
800 SYS "OS_SpriteOp",R0,R1,R2,R3
810 ENDPROC
820 :
830 DEF FNwhich_icon(F%)

```

```

840 I%=0
850 WHILE icon%(I%)<>F% AND I%<max_ty
es%
860 I%+=1
870 ENDWHILE
880 =I%
890 :
900 DEF PROCerror(!block%,$(block%+4))
910 SYS "Wimp_ReportError",block%,1,"S
etType"
920 ENDPROC
930 :
940 DEF PROCinitialise
950 DIM block% 99,menu% 99,b_type% 19,
i_name% 8,i_type% 3
960 max_types%=5
970 DIM icon%(max_types%),type%(max_ty
pes%):icon%()=-1
980 quit%=FALSE
990 SYS "Wimp_Initialise",200,&4B53415
4,"SetType"
1000 PROCcreate_icon(0,"!SetType")
1010 ENDPROC
1020 :
1030 DEF PROCcreate_icon(I%,spr$)
1040 !block%=-1
1050 block%!4=0:block%!12=68
1060 block%!8=0:block%!16=68
1070 block%!20=2:$(block%+24)=spr$
1080 SYS "Wimp_CreateIcon",,block% TO i
con%(I%)
1090 ENDPROC
1100 :
1110 DEF PROCcreate_menu(X%,I%)
1120 menu_icon%=I%:M%=menu%
1130 icon%=FNwhich_icon(I%)
1140 IF icon%=0 THEN
1150 $M%="SetType"
1160 M%!12=&70207:M%!16=192:M%!20=40
1170 M%!24=0:M%!28=4:M%!32=0
1180 M%!36=&7000121:M%!40=b_type%
1190 $b_type%="" :M%!44=-1:M%!48=20
1200 M%!52=&80:M%!56=0:M%!60=&7000021
1210 $(M%+64)="Quit"
1220 SYS "Wimp_CreateMenu",,M%,X%-64,17
6
1230 ELSE
1240 SYS "OS_FSControl",18,,type%(icon%
) TO , ,A%,B%
1250 M%!0=A%:M%!4=B%:M%!8=13
1260 M%!12=&70207:M%!16=192:M%!20=40
1270 M%!24=0:M%!28=&80:M%!32=-1
1280 M%!36=&7000021:$(M%+40)="Remove Ic
on"
1290 SYS "Wimp_CreateMenu",,M%,X%-64,13
6
1300 ENDIF
1310 ENDPROC


```

Jigsaw - A Real Puzzle

Reviewed by Mike Williams

Occasionally, a piece of software appears which is beautifully simple in concept and has immediate appeal. *Jigsaw* by 4mation is just such a program, one which is sure to keep young children enthralled for hours yet, challenging enough for all ages.

The idea is so simple. Take any suitable screen picture, cut it up into jigsaw pieces and jumble these up on the screen. Then use the mouse to select and position pieces to complete the puzzle. The pieces are displayed in the top half of the screen at reduced scale, with the currently selected piece at full size, and a replica, again at a reduced size, of the partially completed jigsaw. Pressing the menu button reveals the jigsaw at full size, and the selected piece can be moved into position (and repositioned again later if at first you get it wrong).



Inserting a piece in a partly completed puzzle

Any of 24 possible levels of difficulty may be selected, cutting a picture into anything from 12 to 120 pieces. You can choose whether pieces are presented the right way up or not, and whether the complete picture should be available for reference while completing the puzzle.



The main jigsaw display showing pieces

What is more, any screen image saved as a sprite may be used as subject matter for a jigsaw, so you can create your own puzzles, using Paint for example. And while *Jigsaw* stores pictures in a highly compressed format, these can be exported as sprites, and sprites loaded and resaved as compressed pictures.

Some 15 superb pictures are supplied as part of the two disc pack, together with eighteen pages of documentation.

This is an unusual piece of software, maybe limited in its application, but a delight to use. And if you think it all sounds too easy, then trying to solve a puzzle at the higher levels of difficulty will tie even the most enthusiastic puzzler into knots - recommended, though somewhat pricey.

Product	Jigsaw
Supplier	4mation Linden Lea, Rock Park, Barnstaple, Devon EX32 9AQ. Tel. (0271) 45566
Price	£33.35 inc. VAT.

RU

INTO THE 90'S WITH DABS PRESS

ARCHIMEDES FIRST STEPS

Beginners Guide to the
Archimedes & BBC A3000

This book is the perfect introductory guide to the Archimedes, to guide you through the first few months of ownership, acting as an easy-to-read supplement to the User Guide.

The book describes in detail how to put the RISC OS Desktop to best use. The Welcome discs contain a wide range of useful programs, and these are fully documented.

But the book also goes beyond this and describes the sort of software and hardware additions available to the Archimedes owner, and how to choose and install them.

The many features of this book include:

- Applicable to all Archimedes with RISC OS
- Using the Desktop, RAMdisc and ADFS
- Edit, Paint, Draw and Maestro
- The Task Manager
- The BBC and PC emulators
- Hardware and software additions
- Illustrated throughout

BRAND NEW - RELEASED 23rd JANUARY

PRICE £9.95

YET ANOTHER POPULAR DABHAND GUIDE

CAMBRIDGE PASCAL

Full featured Pascal Compiler for the Acorn
Archimedes



**DABS
PRESS**

Cambridge Pascal is a comprehensive version of the Pascal language and includes many extra enhancing features over the standard specification including full dynamic string handling, local error handling, random access files, direct access to 'star' commands and RISC OS SWI calls. It is 100% Desktop compatible but can

also be run from the command line. All programs compile into fast, efficient machine code.

Cambridge Pascal requires any Archimedes running RISC OS with at least 1Mb of RAM. Hard discs and extra memory are useful, but the system is perfectly workable with this minimum configuration.

Price £79.95 (£69.52+VAT). Site licences available. Free demonstration disc and full specification sheet available on request.

DEMO DISC FREE ON REQUEST

iNSTIGATOR

THE ARCHIMEDES SYSTEM MANAGER

Instigator is a powerful utility which adds over eighty new commands to RISC OS, and provides you with additional commands for memory management, colour definition, screen display, cut-and-paste, command archiving, etc. Instigator is the *only* command toolkit which allows both Desktop and Command Line operation. Features include:


- Full intelligent memory editor, find and fill
- Colour-coded disassembler
- Disc sector editor (ADFS, MS-DOS etc.)
- Get, put and find bytes on disc
- Load/save of CMOS RAM data, F-Keys etc.
- Line editor with text cut-and paste in any application
- Filename completion from directory list
- Screen dimmer and brightness control
- Smooth text scrolling
- Command line archiving and much much more ...

"...it provides a wealth of very useful features, including just about everything offered by other toolkit packages...if you need a toolkit, then I can highly recommend Instigator." RISC User October 1989

Only £49.95 inc. VAT

FULL ARC CATALOGUE FREE ON REQUEST

All-In Boxing



- Gym, skipping and boxing stages
- Digitised grunts and groans and bells
- Referee counts with real speech
- One or two player game
- Installs on hard disc
- Six different opponents
- Superb graphics

Thrill to the exciting world of championship boxing, Marvel at the realistic graphics and life-like sound and speech, in this new simulation from ace games programmer Mark Dixon. Training in the gym and skipping between rounds to prepare for the big fight with a range of opponents. A knockout!

Only £14.95 inc. VAT
POST FREE

MORE GAMES IN THE COMING MONTHS

Dabs Press products are available from your local Acorn dealer, or in case of difficulty, direct from Dabs Press (Dept. RU1), 5 Victoria Lane, Whitefield, Manchester M25 6AL. Tel. 061-766 8423. Fax. 061-766 8425. Postage free in the UK. Prices shown include VAT. Foreign deduct VAT and add £2.50 (surface/Europe), £12 (air). Payment by cheque, Access/MC or Visa.

Outline Fonts

A Survey by Lee Calcraft

Acorn have recently released their new Outline Font Manager which provides for high quality anti-aliased fonts on the Archimedes (for further details see *Of Printers Drivers and Fonts* in the last issue). These fonts may be used in Draw, and in DTP packages such as Acorn DTP, Impression and the forthcoming Beebug DTP, as well as in users' own programs.

Trinity Medium

Trinity Medium Italic

Trinity Bold

Trinity Bold Italic

Homerton Medium

Homerton Medium Italic

Homerton Bold

Homerton Bold Italic

Corpus Medium

Corpus Medium Italic

Corpus Bold

Corpus Bold Italic

Acorn's Font Starter Pack consists of 3 basic fonts in 4 standard styles

Because of this there is considerable interest in the subject, and a number of companies are marketing (or preparing to market) new outline fonts for the Archimedes. We present here a summary of those fonts which are currently available, and those in the pipeline.

ACORN

As part of their DTP package, Acorn supply the outline font manager with the following 3 fonts in the four styles

medium, medium italic, bold and bold italic:

Corpus (Courier)

Trinity (Times)

Homerton (Helvetica)

Additionally, current versions of their DTP have a limited number of symbol characters, supplied as Selwyn (equivalent to about one quarter of Zapf Dingbats), plus Newhall bold. This latter is a single-style version of New Century Schoolbook.

Acorn are now marketing a number of font packs separately, as follows, each costing £51.75 inc. VAT:

Font Starter Pack

This contains Corpus, Trinity and Homerton in the four standard styles (medium, medium italic etc.), plus the outline font manager. Available early January 1990.

Newhall Font Pack

Newhall (New Century Schoolbook) in the four standard styles. Available early February 1990.

Acorn Symbols Font Pack

Selwyn - a complete symbols set, equivalent to Zapf Dingbats. This may additionally include some mathematical symbols. Available Spring 1990.

All of these fonts are designed for Acorn by Oxford-based Digital Type Systems.

COMPUTER CONCEPTS

Computer Concepts supply the sets of fonts from Acorn's Font Starter Pack (Trinity, Homerton and Corpus in 4 styles), together with the outline font manager as part of the Impression package. Additionally, Impression 1.0 (the release version) will contain the font Greek3, consisting of the Greek alphabet in upper and lower case.

Outline Fonts

Computer Concepts are also working on a Palatino equivalent, projected name *Pembroke* (matching Acorn's Cambridge colleges with an Oxford counterpart). When it becomes available in the new year, this will probably be marketed as a separate disc-based product costing around £20. It may also be included with future versions of Impression.

Greek3

ΑΒΧΔΕΦΓΗΘΚΛΜΝΟΠΘΡΣΤΥΖΩΞΨΖ
αβγδεφγηθκλμνοπθρστυζωξψζ

Pembroke

ABCDEFGHIJKLMNOPQRSTUVWXYZ
1234567890 abcdefghijklmnopqrstuvwxyz

Computer Concepts' Greek3 and Pembroke fonts

Avant Garde

ABCDEFGHIJKLMNOPQRSTUVWXYZ
1234567890 abcdefghijklmnopqrstuvwxyz

Palatino

ABCDEFGHIJKLMNOPQRSTUVWXYZ
1234567890 abcdefghijklmnopqrstuvwxyz

Bookman

ABCDEF GHIJ KLMNOP QRSTUV WXYZ
123456 7890 abcdefgh ijklmnop qrstuv wxyz

Garamond

ABCDEFGHIJKLMNOPQRSTUVWXYZ
1234567890 abcdefghijklmnopqrstuvwxyz

Zapf Chancery

1234567890 abcdefghijklmnopqrstuvwxyz

Schoolbook

ABCDEF GHIJ KLMNOP QRSTUV WXYZ
1234567890 abcdefghijklmnopqrstuvwxy z

Optima

ABCDEFGHIJKLMNOPQRSTUVWXYZ
1234567890 abcdefghijklmnopqrstuvwxyz

Zapf Dingbats

[illegible]

Apple LaserWriter versions of other fonts under development

CLARES MICRO SUPPLIES

When Clares release their DTP, it will be supplied with a number of Acorn fonts together with the outline font manager, but precisely which fonts, has not yet been decided.

BEEBUG

Beebug DTP will contain at least three fonts in the four standard styles, plus the outline font manager. Additionally, Beebug will be marketing a number of font packs on disc in the new year, each containing four different fonts. These are expected to cost around £30-£40 per pack, as follows:

Pack One

- *Helvetica equivalent
- *Avant Garde equivalent
- *Palatino equivalent

Symbols - A greek character set with some additional mathematical symbols

Pack two

- *Courier equivalent
- *Bookman equivalent
- *Garamond equivalent
- Zapf Chancery equivalent

Pack three

*Times equivalent
*New Century Schoolbook equivalent
*Optima equivalent
Zapf Dingbats equivalent

The starred items will be available in the four standard styles (medium, medium italic, bold and bold italic). *RU*

Coloured Text Panels

This program by Barry Christie assembles a module for the speedy display of coloured text panels in mode 15.

The program listed here assembles a module (called SlabModule) which makes the creation of three dimensional coloured panels (referred to as slabs) for text displays extremely easy, and of course fast. The program also contains definitions for five procedures, designed to make the use of the module from your own programs as simple as possible, and the listing also contains a demonstration of the module in action. Note that the module and its use is restricted to mode 15, a 256 colour mode.



Slab module demonstration screen

The source code for the module is in the form of a procedure (starting at line 420), which is called once to assemble and save the module. The procedures which use the assembled module are listed from lines 120 to 400, and these procedures should be included in your own programs where you want to use the slab drawing module. Finally, in the listing, the demonstration procedure is at the end, and is called once after the module has first been assembled.

The module has to be initialised before use by calling PROCinitslab, which tells the module where the resident integer

variables are stored. This is because the module uses these variables when passing parameters back and forth between the program and the module. For convenience, the descriptions below use more meaningful letters to represent parameters.

The other procedures are as follows:

PROCslab(x,y,w,h,t)

This is used to draw a slab on the screen, and the parameters are:

x = x co-ordinate (0-79)
y = y co-ordinate (0-63)
w = width (0-80), h = height (0-64)
t = type (0=raised/1=sunken)

PROCslabcolr(c)

This is used to decide the slab colour. Its parameter is:

c = colour (0=grey, 1=blue, 2=magenta, 3=green, 4=gold, 5=cyan)

PROCtext(x,y,t\$)

This is used to place text on the screen. The parameters are:

x = x co-ordinate (0-79)
y = y co-ordinate (0-63)
t = text

PROCtextcolr(t)

This is used to determine the colour of the text, with parameter:

t=colour
(0=background, 1=foreground, 2=white)

PROCinitslab

This is used to initialise the slab module (see above). The screen base address is returned in A%.

If you are going to use the module from within your own programs you will first

Coloured Text Panels

need to load the module, by double clicking on its icon from the Desktop, or by using the *RMLoad command in your program, e.g.:

```
*RMLoad SlabModule
```

Note: No range checking is used, so if a slab goes off the screen an error will be given.

The module implements three star commands called by the procedures described above. These are:

InitCode <address>

This initialises slab drawing to use the resident integer variables.

SlabColr

This determines the slab colour specified in A%.

ShowSlab

This command draws a slab on the screen using the integer variables A% to E% to supply all information as for PROCslab above.

```
10 REM          >SlabDraw
20 REM Program   Arc Slab Draw Module
30 REM Version   A 1.3
40 REM Author    Barry Christie
50 REM RISC User Jan/Feb 1989
60 REM Program   Subject to copyright
70 :
80 MODE 0:PROCslabmodule(2)
90 MODE 13:PROCslabmoduledemo
100 END
110 :
120 DEF PROCslab(A%,B%,C%,D%,E%)
130 OSCLI("ShowSlab")
140 ENDPROC
150 :
160 DEF PROCslabcolr(A%)
170 OSCLI"SlabColr":backC=A%:foreC=B%
180 ENDPROC
190 :
200 DEF PROCtext(A%,B%,A$)
210 VDU5:PLOT4,A%*16,B%*16+28
220 PRINT A$:VDU4
```

```
230 ENDPROC
240 :
250 DEF PROCtextcolr(backfore)
260 CASE backfore OF
270 WHEN 0 : GCOL 0,backC TINT 192
280 WHEN 1 : GCOL 0,foreC TINT 192
290 WHEN 2 : GCOL 0, 63 TINT 192
300 ENDCASE
310 ENDPROC
320 :
330 DEF PROCinitslab
340 DIM workarea 16
350 workarea!&00=&E5990000
360 workarea!&04=&E58F0000
370 workarea!&08=&E1A0F00E
380 CALL workarea,A%
390 OSCLI("InitCode "+STR$(workarea!&0
C))
400 ENDPROC
410 :
420 DEF PROCslabmodule(opt)
430 DIM codearea &1000:REM 4k
440 zero$=STRING$(12,CHR$0)
450 modulestitle$="SlabDrawing"+CHR$0
460 moduleshelps$="SlabDrawing"+CHR$9+
"1.30 ("+LEFT$(TIME$,15)+")"+CHR$0
470 :
480 FOR pass=4 TO 4+opt STEP opt
490 O%=codearea:P%=&0000
500 [OPT pass
510 .moduleheader
520 EQU &00000000:EQU &00000000
530 EQU &00000000:EQU &00000000
540 EQU moduletitle
550 EQU modulehelps
560 EQU modulecmds
570 .moduletitle
580 EQU modulestitle$:ALIGN
590 .modulehelps
600 EQU moduleshelps$:ALIGN
610 .modulecmds
620 EQU "InitCode":EQU 0:ALIGN
630 EQU initcode
640 EQU &00010001
650 EQU &00000000
660 EQU &00000000
670 EQU "ShowSlab":EQU 0:ALIGN
680 EQU showslabcode:EQU zero$
690 EQU "SlabColr":EQU 0:ALIGN
```

Coloured Text Panels

```
700 EQUd slabcolrcode:EQUs zero$
710 EQUd &00000000
720 .sysinput EQUd &94:EQUd &FFFFFFF
730 .scrnaddr EQUd &00000000
740 .basvalue EQUd &00000000
750 .modtmp0 ; temporary storage area
760 .modtmp00 EQUd &00000000
770 .modtmp01 EQUd &00000000
780 .modtmp02 EQUd &00000000
790 .modtmp03 EQUd &00000000
800 .modtmp04 EQUd &00000000
810 .modtmp05 EQUd &00000000
820 .modvalue ; parameter area
830 .modval00 EQUd &00000000
840 .modval01 EQUd &00000000
850 .modval02 EQUd &00000000
860 .modval03 EQUd &00000000
870 .modval04 EQUd &00000000
880 .initcode
890 STMFD R13!, {R0-R12,R14}
900 MOV R2, #&80000000 ; maximum value
910 MOV R1, R0 ; address of string
920 MOV R0, #&0A ; base to use (ie.10)
930 SWI "XOS_ReadUnsigned"
940 BVS initeror
950 STR R2, basvalue
960 BL scrnbasecode
970 LDMFD R13!, {R0-R12,R15}
980 .initeror
990 LDMFD R13!, {R0-R12,R14}
1000 ADR R0, erortext
1010 ORR R14, R14, #&10000000
1020 MOVS PC, R14
1030 .erortext EQUd &BAD0BEEB
1040 EQUs "Cannot Initialise"
1050 EQUb &00:ALIGN
1060 .loadbasval
1070 LDR R10, basvalue
1080 ADR R11, modvalue
1090 LDMIA R10, {R0-R4}
1100 STMIA R11, {R0-R4}
1110 MOV R15, R14
1120 .savebasval
1130 LDR R10, basvalue
1140 ADR R11, modvalue
1150 LDMIA R11, {R0-R4}
1160 STMIA R10, {R0-R4}
1170 MOV R15, R14
1180 .scrnbasecode
1190 STMFD R13!, {R0-R12,R14}
1200 ADR R0, sysinput
1210 ADR R1, scrnaddr
1220 SWI "XOS_ReadVduVariables"
1230 LDMVSFD R13!, {R0-R12,R15}
1240 LDR R0, scrnaddr
1250 STR R0, modval00
1260 BL savebasval
1270 LDMFD R13!, {R0-R12,R15}
1280 .calcscreenxy16
1290 STMFD R13!, {R14}
1300 RSB R1, R1, #&40
1310 LDR R14, scrnaddr
1320 ADD R0, R14, R0, ASL, #&03; SB*X*8
1330 MOV R14, #&A00
1340 MLA R0, R1, R14, R0
1350 LDMFD R13!, {R15}
1360 .showslabcode
1370 STMFD R13!, {R0-R12,R14}
1380 BL loadbasval ; get parameters
1390 ADD R1, R1, R3
1400 BL calcscreenxy16
1410 STR R0, modtmp00
1420 SUB R2, R2, #&02 ; x border bit
1430 STR R2, modtmp01 ; slab x width
1440 SUB R3, R3, #&02 ; y border bit
1450 STR R3, modtmp02 ; slab y width
1460 ADR R0, slabdata ; base addr of
1470 CMP R4, #&01 ; slab information
1480 ADDEQ R0, R0, #&120
1490 STR R0, modtmp03
1500 ADD R0, R0, #&60
1510 STR R0, modtmp04
1520 ADD R0, R0, #&60
1530 STR R0, modtmp05
1540 LDR R10, modtmp03
1550 LDR R11, modtmp01
1560 MOV R12, #&01
1570 BL drawslabline
1580 LDR R10, modtmp04
1590 LDR R11, modtmp01
1600 LDR R12, modtmp02
1610 BL drawslabline
1620 LDR R10, modtmp05
1630 LDR R11, modtmp01
1640 MOV R12, #&01
1650 BL drawslabline
1660 LDMFD R13!, {R0-R12,R15}
1670 .drawslabline
```

Premier 3

The Archimedes Text Processor

Full word processing of -

- * Invoices
- * Reports
- * Letters
- * Statements
- * Circulars
- * Etc.

PLUS -

Quantity	Product	Price	Total
1200	Widgets	£ 29.95	£ 35940.00

Dynamic Text

Premier's unique Dynamic Text feature is a simple yet powerful concept which puts you the user in complete control for the first time. It provides -

- * Automatic data linkage between documents.
- * Flexible control over document formatting.
- * The simplest printer control yet devised.

A New Type of Program

Premier's Dynamic Text and powerful command language combine to provide the best solution to text processing problems at home or in the office. It puts the user in greater control than ever before, by offering greater freedom and flexibility. All program functions may be modified by the user, while command macros may be written to meet any specific user requirement.

All this is available from just one program, which is fully multi-tasking under RISC-OS, and comes complete with 220 page user guide, separate word-processor manual, key strips, and new 10,000 word thesaurus, for just £120 plus VAT.

Premier 3 will be available from the 1st December 1989. This definitive version includes fast 'in memory' data transfer between other applications, extended spreadsheet functions, and faster screen refresh. New facilities allow the independent control of screen and printer output. Older version discs may be upgraded free of charge (including full notes on disc), or complete with the new word processor manual and thesaurus, for £17.35 + VAT.

Circle Software

33, Restrop View,
Purton, Swindon,
Wilts. SN5 9DG
Tel: 0793 770021

Premier 3 may be purchased directly by phone, quoting your MasterCard (Access) or Visa card number, or from your nearest Acorn dealer. Educational discounts and multi-machine licences are available.

Coloured Text Panels

```
1680 SUBS R12,R12,#&01
1690 MOVMI R15,R14
1700 MOV R1,#&04
1710 MOV R2,R10
1720 .nowdrawline1
1730 LDR R0,modtmp00
1740 ADD R4,R0,#&280
1750 STR R4,modtmp00
1760 MOV R3,R11
1770 LDMIA R2!,{R4-R9}
1780 STMIA R0!,{R4-R5}
1790 .nowdrawline2
1800 SUBS R3,R3,#&01
1810 STMPLIA R0!,{R6-R7}
1820 BPL nowdrawline2
1830 STMIA R0!,{R8-R9}
1840 SUBS R1,R1,#&01
1850 BNE nowdrawline1
1860 B drawslabline
1870 .slabcolrcode
1880 STMFD R13!,{R0-R12,R14}
1890 BL loadbasval ; get parameters
1900 MOV R1,#&08
1910 ADR R2,slabcolr
1920 MLA R1,R0,R1,R2
1930 ADR R0,slabdata
1940 ADR R2,slabmaps
1950 MOV R3,#&90
1960 .slabcolrloop
1970 LDRB R4,[R2],#&01
1980 MOV R5,R4,LSR#&04
1990 AND R4,R4,#&0F
2000 LDRB R6,[R1,R4]
2010 STRB R6,[R0],#&01
2020 STRB R6,[R0],#&01
2030 LDRB R6,[R1,R5]
2040 STRB R6,[R0],#&01
2050 STRB R6,[R0],#&01
2060 SUBS R3,R3,#&01
2070 BNE slabcolrloop
2080 LDR R0,basvalue
2090 LDRB R2,[R1,#&06]
2100 STR R2,[R0,#&00]
2110 LDRB R2,[R1,#&07]
2120 STR R2,[R0,#&04]
2130 LDMFD R13!,{R0-R12,R15}
2140 .slabcolr
2150 EQUED &2FD32DD1:EQUED &3F15FFFD

2160 EQUED &0BA709A5:EQUED &3A10DBD9
2170 EQUED &0FB30DB1:EQUED &3B11DFDD
2180 EQUED &234F214D:EQUED &2E04F3F1
2190 EQUED &2BC729C4:EQUED &3E14FBF9
2200 EQUED &073B0539:EQUED &2B01D7D5
2210 EQUED &275B2559:EQUED &2F05F7F5
2220 .slabmaps
2230 EQUED &00000000:EQUED &22201000
2240 EQUED &13222222:EQUED &44444420
2250 EQUED &54201304:EQUED &13025555
2260 EQUED &44445420:EQUED &54201302
2270 EQUED &13024444:EQUED &44445420
2280 EQUED &54201302:EQUED &13024444
2290 EQUED &22222420:EQUED &00201302
2300 EQUED &13000000:EQUED &33333330
2310 EQUED &11111333:EQUED &11111111
2320 EQUED &22222222:EQUED &00025222
2330 EQUED &54000000:EQUED &33333302
2340 EQUED &13025423:EQUED &54201111
2350 EQUED &33331302:EQUED &13025420
2360 EQUED &54203333:EQUED &33331302
2370 EQUED &13025420:EQUED &54203333
2380 EQUED &00003032:EQUED &22025420
2390 EQUED &54222222:EQUED &44444442
2400 EQUED &55555444:EQUED &55555555
2410 .slabdata
2420 EQU STRING$(144,CHR$0)
2430 EQU STRING$(144,CHR$0)
2440 EQU STRING$(144,CHR$0)
2450 EQU STRING$(144,CHR$0)
2460 |
2470 NEXT pass
2480 SYS "OS File",&0A,"SlabModule",&FF
A,,codearea,0%
2490 ENDPROC
2500 :
2510 DEF PROCslabmoduledemo
2520 *RMLoad SlabModule
2530 PROCinitslab
2540 REPEAT
2550 scol=RND(6):tcol=RND(2):xco=RND(40
):yco=RND(32)
2560 PROCslabcolr(scol):PROCslab(xco,yc
o,RND(40),RND(32),RND(100) MOD 2)
2570 PROCtextcolr(tcol):PROCtext(xco+1,
yco+1,"testing")
2580 UNTIL FALSE
2590 ENDPROC
```

RU

A Voice Module Generator

Felix Andrew describes an innovative program which will create a voice module from a user-generated waveform.

The program is supplied only on this month's magazine disc.

The sound system of the Archimedes comes equipped with nine so-called voices (see Into the Arc, RISC User Volume 3 Issue 1). However, the possibilities of these can soon become exhausted.

This application allows you to generate additional voices easily and simply from a waveform. There are two ways to generate the shape of this. Firstly, you can draw the shape of the waveform in a window using the mouse. Secondly, you can use a mathematical formula to generate the waveform.



Waveform window showing default calculated shape

The waveform, once created, can be saved in two different ways. It can be saved in its simple form as a small 256 byte data file. These data files can be further edited as required. The waveform can also be saved in the form of a relocatable voice module. Once it has been saved like this, the voice can be used in Maestro (on Applications Disc 2) or like any other voice (see again the article in RISC User Volume 3 Issue 1).

INSTALLING AND USING THE APPLICATION

The program is supplied on disc as an application called !VoiceGen. Double

clicking its icon in the directory viewer will install the application on the icon bar. Clicking on this with the Menu button will reveal four options, of which Info and Quit should be self-explanatory.

There are two save entries - Create Module and Save Waveform. The Save Waveform entry saves a data file of 256 bytes which represents just the shape of the waveform. Once you have saved the waveform, it can be modified at a later date by dragging the data file to the application icon on the icon bar.

The Create module will create and save a relocatable voice module. Voice modules can be installed easily by double clicking on their icons from the Desktop or by using *RMLOAD <module name>. However, these relocatable modules cannot be loaded back into the application to allow any further modification of the waveform.

If you save a waveform as data (by dragging the 'data' icon from the Save as: window to a directory viewer), the program will add an 'm' to the end of the same file name if you then choose to save the same waveform as a voice module. This makes it simple to save a waveform as both data and module.

If you click with the select button on the application icon the Waveform window itself will be displayed. This shows the current voice waveform and allows real-time editing.

THE WAVEFORM WINDOW

When you click in this window with the select button you can directly create or alter the shape of the waveform. If you move the mouse too quickly while drawing, you may find that 'spikes' appear. This is because the application is not notified quickly enough by the Wimp to deal with intermediate mouse positions. If the mouse is moved smoothly and slowly this problem can be avoided.

The menu button will cause the Wave form menu to be opened. There are two entries - Defaults and Construct. Defaults gives you the option of setting the waveform to one of three standard shapes: Sine Wave, Square Wave and Sawtooth. The Construct entry allows you to define the shape of the waveform using simple expressions. This may be a little mathematical for some, but it doesn't hurt to play around with it for a while, as we shall see.

CONSTRUCTING EXPRESSIONS

The expression that you type in is taken as the function of the time variable 'X'. X is measured in radians to make things easier later on. It takes values from 0 to 2π . To make it a bit easier to understand, just type in the number 128. You will see that you get a horizontal line in the middle of the waveform. The bottom value of the waveform is zero, and the top value is 255, so the middle value is 128.

A simple sine wave can be created by typing in: $(\sin(X)*128)+128$. The reason why the sine is multiplied by 128 is that a sine normally gives values in the range -1 to +1. We need to magnify this amplitude by 128 to give a range of -128 to +128 to fill the window. However, the window accommodates values in the range 0 to 256, so a further 128 is added on to the expression to compensate for this.

If you want a sine wave of twice the frequency, two peaks instead of one, then you would type in: $(\sin(2*X)*128)+128$. We use $2*X$ which doubles the step size, so you get twice as many peaks in the waveform. If you had typed $3*X$, then you would get 3 peaks and so on.

The more peaks, the higher the frequency. The number you use to multiply by is called the harmonic. To use two harmonics you might try:

$$128 + (\sin(3*X) + \sin(5*X)) / 2 * 128$$

which will result in a waveform which might look a little odd but it sounds subtly different to a normal sine wave. Note the division by 2 now that two sine waves are added together.

You may also decide to alter the amplitude of the harmonics. In this case you will have to take care in deciding by how much to multiply each individual harmonic (sine). If you wanted a dominant harmonic with twice the amplitude of the other then you could try:

$$128 + (2 * (\sin(3*X)) + (\sin(5*X))) * 128 / 3$$

This method of designing waveforms is quite complex; the best approach, as always, is to experiment.

LISTENING TO A WAVEFORM

To hear how any waveform sounds, proceed as follows. First save the data and create a module. Once the module has been saved, double click on it from the Desktop. It has now been loaded into memory. If you type *VOICES you will see that a new voice has been created (the voice name is the same as that for the module). You can now attach a channel to the voice by typing:

*Channelvoice 1 <voicename>

If you now press the Copy key or Ctrl-G, you will be able to hear the new voice. Alternatively, use:

SOUND 1, -15, <note>, <duration>

where note is in the range 1-255 and duration is in the range 0-254.

To summarise, the steps involved in creating and playing a new sound are:

1. Draw or construct a waveform.
2. Use Save Waveform and save it as a data file (say, NewBell).
3. Use Create Module to create and save the relocatable module. Simply open the save window and click on OK.
4. Double click on the RM NewBellm.
5. Press F12.
6. Type *VOICES
7. Type *CHANNELVOICE 1 NewBellm
8. Press the copy key or Ctrl-G.

Remember to press Return to get back to the Desktop. You can also speed things up when experimenting, by saving waveforms to a RAM disc.


INSTALLING VOICES

After re-editing a waveform for a voice already in use, you will need to both reload the voice module and re-assign the voice to a channel using *ChannelVoice, otherwise no sound is likely to be heard.

RU

ARCHIMEDES SOFTWARE


HOME ACCOUNTS £49.95



Keep your home or club finances in order. Full control of multiple bank accounts including credit cards and building societies. Budgeting facility to assist cashflow prediction. Graphs of budgets and expenditure. Caters for standing orders, transfers, statement reconciliation, etc. (Multi-tasking if using RISC OS.)

Prices
inclusive
of VAT.

ANCESTRY £79.95



The ultimate in computerised genealogy! for use in families or pedigree animals. Use added card index for extra data or photos of individuals. Demo file contains illustrated Royal Family tree. Vertical or horizontal printout of family tree. For home, hobby or educational use. (RISC OS compatible)

Access &
Barclaycard
accepted

ATELIER £99.95



Professional quality art package. Probably the most sophisticated sprite editor available. Animation of image sequences with Quantel-style graphic effects. Anti-alias squashing, rotation of areas into any quadrangle, and sprite and brush patterning. Further features allow TV-style techniques to even wrap a picture around a 3D surface. (Multi-tasking if using RISC OS.) (To be released soon).



69 SIDWELL STREET, EXETER. EX4 6PH Tel: (0392) 437756 Fax: (0392) 421762

System Fonts

We provide 10 new system fonts on the magazine disc. Alan Wrigley explains what they are, and how to manipulate the resident font.

With all the attention currently being lavished on Acorn's new Outline Fonts, the poor old standard System Font has been rather neglected. This short article sets out to rectify that situation.

The System Font is the one you normally see when the machine is first switched on. The characters are formed on an 8x8 pixel grid, exactly as was done on the BBC Micro. In addition to the standard ASCII characters (codes 32-126), the Archimedes has an extended character set from 128-255, any and all of which can be accessed from the keyboard by holding down the Alt key, entering the character code on the numeric keyboard, and then releasing the Alt key again. For example, hold down Alt, type in 169 on the numeric keypad and release Alt - you will get a copyright sign on the screen. This set includes accented characters, some Greek letters, and a number of symbols. To display the whole of the extended character set, use:

```
FOR A=128 TO 255:P.;A"CHR$A,;:NEXT
```

Just as on the BBC Micro, the characters can be redefined by using VDU23,<character code>,x1,x2,x3,x4,x5,x6,x7,x8 where x1 to x8 contain the pixel information for each of 8 rows from top to bottom, with the most significant bit of each byte representing the pixel to the left. Each bit which is set denotes a pixel which is to appear in the character. For example:

```
VDU23,165,102,60,24,24,126,24,24,0
defines character 165 as a yen sign (see Figure 1).
```

However, the Archimedes also provides the facility to store system fonts on disc and then load them back into the machine later. A system font file is given a filetype of FF7 (BBC Font), and consists simply of a string of bytes, 10 per character, which represent

all the VDU codes, starting from the initial '23', required to redefine whichever characters you wish to alter in the range 32-255. Double-clicking on a file with this filetype causes a *PRINT operation to be performed on the file, which effectively defines the new font immediately.




Figure 1

Creating system font files is very simple. The easiest way is to use a short Basic program similar to the one given below.

```
10 REM TO REDEFINE n CHARACTERS
20 F=OPENOUT"MySysFont"
30 FOR I=1 TO n*10
40 READ X:BPUT# F,X
50 NEXT
60 CLOSE# F
70 *SetType MySysFont FF7
80 END
100 DATA 23,32,0,0,0,0,0,0,0,0,0
110 DATA 23,33,.....
120 DATA .....
```

Note that n should be set to the number of characters to be redefined. The example assumes we are redefining characters from code 32 upwards (the start of the printable characters).

System Fonts

Instead of line 70 you may also set the filetype after the font file has been created by using the Set Filetype application described elsewhere in this issue.

1. Bold	ABCDEFGHIJklmnpqrst
2. Double	ABCDEFGHIJklmnpqrst
3. Halfsize	ABCDEFGHIJklmnpqrst
4. Hitec	ABCDEFGHIJklmnpqrst
5. Newfont	ABCDEFGHIJklmnpqrst
6. Slant	ABCDEFGHIJklmnpqrst
7. Square	ABCDEFGHIJklmnpqrst
8. Thick	ABCDEFGHIJklmnpqrst
9. Thin	ABCDEFGHIJklmnpqrst
10. Uppercase	ABCDEFGHIJklmnpqrst

Figure 2

Since the file contains nothing but VDU codes, there is nothing to stop you including other VDU sequences in the file

if you wish, for example palette information using VDU19. In fact, it is perfectly possible to append a palette file onto the end of a font file, although not the other way around as the run action for a palette file is different.

The hardest part, of course, is redefining the characters in the first place. This is made a lot easier by the use of a character designer, such as !CharDes which appeared on the RISC User disc for Volume 3 Issue 2, which will generate complete font files from designs entered via the mouse.

This month's magazine disc contains 10 complete font files, which are shown in Figure 2. Any of these can be installed by double clicking on the font's icon from the Desktop. This font then becomes immediately active.

RU

ARCHIMEDES	Disc 1	EMACS. Super editor with language. Now includes full C source.	SOFTWARE
	Disc 2	MicroSpell. 43,000 word real time spelling checker module.	
	Disc 4	XLISP. Object oriented version of LISP with C source and progs.	
	Disc 5	C Toolkit. 20+progs for C programmers with sources. grep, awk,...	
	Disc 6	Kermit. Archimedes, BBC and MSDOS versions of comms. prog.	
	Disc 7	WIMP Chess. Good wimp based chess game with many features.	
	Disc 8	CrossStar. wimp based crossword solver with huge dictionary.	
	Disc 10	More C Tools. yacc and lex with examples and C source. diff etc.	
	Disc 11	Little SmallTalk. original object oriented language with C source.	
	Disc 14	GNU Tools#1. high quality tools with source. egrep, sed, awk, diff.	
	Disc 15	Clip Art#1 50 pictures, also 65 Epson LQ printer fonts, ISparkplug	
	Disc 16	Spark. Super RISC OS wimp based multitasking file/directory archiver. !Backdrop sticky desktop, pd progs, 1Mb. colour pics.	
	Disc 18	MTV Raytracer. database driven 3D raytracing package with C source code. Lots of fun making pretty raytraced pictures.	
	Disc 19	Starchart. wimp multitask program to make Draw file starmaps showing positions of stars and planets. Catalog of 9000 stars.	
	Disc 20	GNU Tools#2. gnumake. CXRF C source code cross ref. dbase. Xfmt simple nroff, pr formatter, M4 macro language. with C srcs.	
	Each disc is £5.99 inc. Buy four claim another free!		
	David Pilling, P.O. Box 22, Thornton Cleveleys, Blackpool. FY5 1LR.		
	Free Air Mail delivery on overseas orders. Full list available on request.		

Into the Arc - Desktop Publishing with Draw

Richard Mawhood explains how to use the Draw application for simple desktop publishing

I suspect that many readers are put off desktop publishing by the cost and apparent complexity of the available dedicated software, particularly if they are not really sure if this is the best way to go about it. Plenty of people have pointed out that you can do quite a good job with scissors, glue and a simple word processing system. However, RISC OS users have better opportunities to experiment without going in for all the sophistication, and at no cost at all!

I teach in a secondary school, and I wanted to produce some articles in a magazine format for my sixth-form class; to cap it all, in a foreign language (French)! 1st Word Plus copes superbly with almost all my word processing needs; foreign text is no problem - it has the easiest method I've yet seen for obtaining accented characters. But it can't produce text in columns, which was what I was after.

This is where the Draw application (supplied on Applications Disc 2) comes in - on page 117 of the User Guide I read that Draw can format text into columns. Great! I started work right away, and ... nearly gave up a few times ..., but a week later, I had the final product - and a much better understanding of the manual, the various applications used, and some of the limitations that exist. I hope that sharing my experiences will save you time and frustration if you try this for yourself.

It's probably easiest to prepare your text with a word processor or you can use Edit; headlines are best done like this too, but separately from the main text, as this gives you most control over their final appearance. All of this must be saved without the embedded style and format control codes, i.e. not in word processing mode. Control over the way the text

appears in Draw is obtained by inserting a text "header", which allows any of the following to be specified:

- justification
- font and font size
- number of columns
- line spacing
- margins
- text colours
- various miscellaneous features

Each specification in the header consists of an abbreviated form of command always commencing with the 'back-slash' character '\'. These are defined in the (new) User Guide on pages 118 to 125. For example, I used this header for the main body of the article:


```
\!1      - tells Draw that this is text
\AD      - justified both left and right
\D2      - in two columns
\F0 Trinity.Medium 10 - font number
0 is 10-point Trinity
\L10     - 10-point line spacing
\M0 0    - no margins, right or left.
These are the margins for each column,
not the page
\P10     - extra paragraph spacing of
10 points. The text then begins with: \0,
meaning that text follows immediately in
font number 0.
```

The header effectively defines the so-called *text area* in Draw. You can also put more of these commands within the text, for example to change font and line spacing. You can even include comments to yourself which won't be printed, so you could outline your ideas for an article with a series of comments before writing the text in full (very structured).

This bit was easy; the text was written in 1st Word Plus including the header commands, and I could experiment with

how it looked on the page by altering the header (using Edit, so that all the rest of the work was done from the Desktop). I suggest that you specify plenty of columns in the header; if you don't use one, it simply doesn't appear.

There is a problem with ordinary Return characters - e.g. at the end of a paragraph - as they simply get ignored. To force a line break, you have to enter '\ ' before pressing Return itself. Alternatively, at the end of a paragraph, if you leave an empty line, Draw will insert between the paragraphs whatever space you specify in the header.



Part of this article in a Draw text area

An initial reading of the User Guide on this subject may appear quite daunting, but persevere, and above all be prepared to experiment until you begin to get a feel for what is going on.

Before starting Draw, it's best to enlarge the font cache using the task display window. I used at least 80K, which speeds up redrawing the screen considerably. Text in Draw can only use outline fonts, not system fonts. You may also need to load first the fonts supplied on Applications Disc 1 (by double clicking on the Fonts folder in the directory viewer for this disc) before proceeding.

So having created your text file, with appropriate header, the next step is to install Draw (if not already present). Then

when you have opened a Draw window, it is quite helpful to have a second view reduced to a quarter size (a sort of mini-page) to show the overall appearance. You can get a "new view" through the *Miscellaneous* option in the Draw menu; when it appears, reduce its size using the *Zoom* facility (e.g. use 1:4).

You must also be aware of the paper limits; using the *Miscellaneous* option again, set the paper size - A4 or whatever - and either "portrait" (longest side vertical) or "landscape" (longest side horizontal). Then click on *Show*, and the Draw windows will show quite clearly which parts of the window you can use.

You may want to draw column guides to ensure that columns of text are of even width; select the rectangle drawing tool from the Toolbox frame (or use Menu and select the *Enter* option followed by *Rectangle*). Click anywhere in the Draw window and drag out a box - the size and shape doesn't matter initially.

Then go into *Select* mode (the bottom-most tool, or by using the Menu button again), and click anywhere on the box outline; a dotted red outline with two "ears" will appear. You can now drag the box until its top left corner is in the required position; then point to the lower "ear" and pull the box out to the required shape and size. Turning on the *Grid* helps to ensure that you get the right column widths. For A4 paper in "portrait", I suggest the following widths: for 2 columns, 3 3/4 inches, for 3 columns, 2 5/12 inches, and for 4 columns, 1 3/4 inches. This allows for gaps of about 1/4 inch. For A5 in "portrait" or A4 in "landscape", columns 2 1/4 inches wide give 2 or 4 columns on the paper. It is worth saving these page layouts just as they are so as to avoid the need to recreate one every time you need it.

Now to start in earnest! Click on Menu and make sure you are in *Select* mode. You can banish the Toolbox so as to see the whole of the work area. Drag the previously prepared text file from its

directory window right onto the Draw window, then enlarge this window to full size. Use the window control icons to make the mini-page visible as well, and hide any other windows in the same way.

You will probably be surprised to find that the columns of text which appear have, in all probability, totally ignored your column guidelines. This is normal. If you click once on any piece of text you will see a red dotted rectangle surrounding the whole of the text area created. Double clicking on a section of text similarly reveals the column containing that piece of text.

To adjust any column proceed as follows. Point to the little bit of text you can see, and click Select repeatedly until you get a dotted red outline (with two "ears") round the column you're interested in. You can now move this column or resize it as you would when drawing rectangles (using your preset guidelines if present). Click on Adjust, and the outline disappears from the column you're pointing at. You'll see how the text fills up the available space, and you can play with the sizes of the columns until you have the balance you want. The dotted red outlines appear on the mini-page as well, and in some cases it is easier to do the moving and reshaping in rough here, as you can see the whole page at once. Then you can "fine-tune" on the full-size image.

Remember that unlike genuine DTP packages you can only work with one sheet of paper. If you want to create a multi-paged document, you will need to create separate text files for each page. This is helped by the fact that text can be exported from Draw back to a file. So create your text, and lay it out on the page. Then re-edit the original text file to create the text for the second page and proceed with that and so on. Saving text from Draw is achieved by selecting *Text area* from the *Save* menu (but select the whole text area first).

To fit in a picture, use two text sections, one above and one below the space reserved. Unless you're using a

scanner, or pictures from disc, it's probably easiest to leave a space for graphics and stick them in later with glue. However, you can easily create borders, lines and more using Draw.

When your document is complete with text and artwork, save it as a standard Draw file.

Finally you need to print your work. Once I had some text in Draw, I wanted to assess the results, so I installed the dot-matrix printer driver from the Desktop and tried to print from the Draw menu. Masses of line feeds and a few lines of garbage ... not much use! I saved the file and tried again, by dragging the file onto the printer icon on the desktop icon bar. Same result. This was where I nearly gave up. Those of you in the know will think me incredibly stupid, but from the little I'd read in the reviews, I thought it was that simple.

For those users who, like me, haven't used the RISC OS printer drivers before: you have to select a driver to suit your particular printer! You do this by clicking Select (no, NOT Menu) on the printer icon when you have installed it on the desktop icon bar. A dialogue box appears, and you can cycle through a list of printer drivers by clicking Select (forwards) or Adjust (backwards). I ended up with the highest resolution on offer: 240 x 216 dots per inch. It is the slowest, but provides the best quality, which is particularly important when using small font sizes.

By the end of it all, I had a tremendous feeling of satisfaction as a result, I think, of having turned Draw to good use, and because I had to do quite a lot myself. I hope you enjoy this as much as I did. Good luck!

Note: The quality of printout produced in this way depends solely on the type of printer used.

RU

We would be interested to hear from other RISC User readers who feel that they could usefully contribute to our series, *Into the Arc*.


PRODUCT NEWS FOR A USERS!

SCSI CARD AND DRIVE

Everything you need to upgrade your A3000 or Archimedes.


Interface card £149.00+VAT from

Hard Drive Kits £375.00+VAT from



PRESENTER II

RISC OS based graphics package (graphics, charts etc ...) for education and business.



£39.95+VAT

PRESENTER STORY

A series based presentation software that allows you to make slides and o.h.p.'s obsolete.

£199.95+VAT



Coming Soon...

COLOUR CONVERTER

Software and hardware card for capturing full colour images using the monochrome Watford Digitiser and colour video equipment.

£169.95+VAT



Education discounts and site licences for software are available.

COLOUR DIGITISER

Single card real-time full colour digitiser for Archimedes



**SALES HOTLINE
098 685 477**

**L I N G U I T Y
P R O F E S S I O N A L**

Wood Farm, Linstead Magna, Halesworth, Suffolk IP19 0DU

Please send me more information about: SCSI ☐ Presenter II ☐ Colour Converter ☐
Presenter Story ☐ Colour Digitiser ☐

Name _____ Address _____

Tel No. _____

LINGENUITY, Wood Farm, Linstead Magna, Halesworth, Suffolk IP19 0DU

Tel: 098 685 477



ADDISON
LINDS INTERNATIONAL
LTD

RU

Clares' Artisan 2

Reviewed by Mike Williams

Artisan was one of the first art packages released for the Archimedes (reviewed in RISC User Volume 1 Issue 1), and unlike many others released in those early days has stood the test of time. Indeed, its success has been sufficient to persuade Clares that a new version was warranted. So what does Artisan 2 have to offer both existing users (of Artisan) and potential first time purchasers?

First and foremost, Artisan 2 is a full RISC OS application running in multi-tasking mode, but Clares has resisted the pressure to put the main painting area within a window. Instead the full screen display is still used, which many may feel is a good move anyway. It certainly avoids the need for any scrolling to see the whole picture, but by the same token the picture size is limited by the screen size, and it is, of course, impossible to see two or more pictures (or parts thereof) on screen at the same time.



New Artisan 2 demo screen showing main menu

This is not to say that Artisan 2 avoids windows altogether. Certain sub-menus, for example the filing sub-menu, generate standard Wimp windows. Control is by way of pictorial menus as before. However, Clares has bowed to the weight of pressure, and menus no longer disappear the instant

the pointer moves off the menu, but only when the user starts performing the selected function. This is an improvement, but I found that on occasion the menu covered vital areas of the current picture as I was about to commit brush to paper, a characteristic I found disconcerting. Yes, the menu can be moved, but I would prefer to select my painting function positively, so that the menu then disappeared. Although Clares says it has carried out extensive user research, I feel that this is really a matter of personal preference. Perhaps the best solution would be a more flexible approach, permitting users to choose the system which suits them best. In fact, Artisan 2 allows the user to revert to the original style of menu operation, if preferred.

The new Artisan provides much the same facilities as the original (still using mode 12), with a variety of brushes, sprays and other colouring and drawing functions. However, new or extended features have been added to most options. For example, the *Fill* function now allows sprite, circular and graduated line fills. The so-called *transparent* colour allows as many colours to be selected for this feature as required.

There are three new sprite functions. You can cut out irregularly shaped sprites, and a *mask* allows drop shadow effects to be produced which mirror the sprite shape. The *distort* function is completely rewritten, and now works with the current sprite, allowing this to be distorted over any closed shape. A *scaling* option also allows sprites to be scaled and reportioned as required.

Saving and loading of pictures (and sprites) can now be accomplished by *dragging*, but the filing menu window has been retained for compatibility. I am not sure why this should be so, as the print menu has completely disappeared in

favour of the standard RISC OS printer drivers (copies of which are included on disc) and printing techniques. An additional utility supplied by Clares now allows either process or spot colour separations to be produced.

One feature introduced to meet teaching needs is the facility to restrict the range of painting functions available to a user, so that children do not encounter unexpected and unwanted features.

Artisan 2 is packaged up in Clares' new colourful and glossy style, with two discs and a completely new 90 page manual. A (disappointingly) small number of new demo screens is supplied as well. However, I do not like Clares' current fad for gluing the back cover of the manual into the packaging, nor do I like the use of colour coding for security every time Artisan 2 is loaded.

At £59.95 for the complete package, Artisan 2 is an excellent introduction to the world of painting by computer, but the upgrade price of £30 for existing users seems just a little high (bearing in mind the £39.95 cost of the original). And remember that Clares' Pro-Artisan now costs £99.95. Potential first time purchasers should also consider *Art Nouveau* from Computer Assisted Learning Ltd (reviewed in RISC User Volume 2 Issue 5) which costs just £42.50 inclusive.

Product	Artisan 2
Supplier	Clares Micro Supplies 98 Middlewich Road, Northwich, Cheshire CW9 7DA. Tel. (0606) 48511
Price	£59.95 inc. VAT. Upgrade from Artisan £30.00 inc. VAT (Both available from BEEBUG Retail)

For reference, Computer Assisted Learning Ltd are at Strathclyde Business Centre, New Stevenston, Strathclyde, Scotland ML1 4JB, tel. (0698) 733775.

RU

"FIRST"

ADVANCED STATISTICAL SYSTEM

For Acorn Archimedes; BBC Models B, B+ and Master; "Industry Standard" machines

A powerful and practical tool for Research, Industry, Business, and Teaching

- Integrated, interactive, robust, fast, accurate, modular. Designed to facilitate data critique.
- Many data entry options. Full data management and formatted display. Extensive data transforms.
- Handles missing values and data subsets. Scatterplots, regression plots, function plots.
- Univariate statistics. Paired and unpaired t tests. Chisquare tests. Nonparametric methods.
- Unrivalled REGRESSION facilities eg weighted, through the origin, standardised. Full statistical information.
- Residuals, fitted and predicted values. Much more. Correlations. ANOVA. Contour plots of regressions.
- Regression DIAGNOSTICS - VIFs, influential points etc. Automatic warnings.
- ROBUST regression - many influence functions. Powerful NONLINEAR least squares
- Time Series, eg moving averages, exponential smoothing, causal models.
- One- Two- and Three-way ANOVA subsystems. Distributions generator. Histograms. Linear Calibration.
- Cluster analysis. Many other powerful analytical and descriptive features. Full utilities.

Price £120-£180 (machine and version dependent). Special RISC USER discount available.

There's far too much to describe here. Get full information now from:

Serious Statistical Software, Lynwood, Benty Heath Lane, Willaston, South Wirral L64 1SD Tel. 051 327 4268

Using Laser Printers

The Panasonic KX-P4450

by Lee Calcraft

The Panasonic KX-P4450 is a middle of the range LaserJet compatible laser printer. It is supplied with a number of emulation modes, and comes with ten resident fonts. Unfortunately of the ten, eight are different sizes of Courier. The other two are proportionally spaced Schoolbook - see figure 1. However, more fonts may be added either by downloading, or by using a font cartridge. The basic laser engine is relatively fast, with a rating of 11 pages per minute. The standard 4450 comes with only half a meg of RAM, but this is upgradable to 1.5Mbytes at a cost of around £340 inc. VAT.

Courier 12 pt
Courier 12 pt italic
Courier 10 pt
Courier 10 pt italic
Courier 8 pt
Courier 8 pt italic
Courier 7.2 pt
Courier 7.2 pt italic
Century 10 pt
Century 10 pt italic

Figure 1. The 4450's ten resident fonts

The whole unit is well packed, and comes with a nicely finished manual which is very helpful on setting up the printer, renewing the toner, etc., but which becomes unhelpfully terse when it comes to making use of the printer's many features by sending control codes.

The 4450 is not the smallest of laser printers. It weighs a hefty 56lbs, has a largish footprint of 16in by 18in, and stands some 14in high. In addition you need a




clear 12in or so to the right of the printer for the paper trays. Two come as standard, and there is also an optional envelope feeder for printing directly onto envelopes of up to 90gsm - but there is no single-sheet feed mechanism for one-off items.

The paper feed in the 4450 is from right to left along the bottom of the printer, and by the time that the paper reaches the left hand end, all printing functions have been completed. The paper is then sent upwards, and over to emerge face down on a tray at the top of the machine. This means that a set of pages will emerge in the right order, and without the inconvenience of a collection tray protruding at the left of the printer, albeit at the cost of a slightly convoluted paper path. However, in several months of use I have only had one paper jam, and this was easily cleared, since access to all parts of the paper path is easily achieved.

CONSUMABLES

In some laser printers all consumable items, including the toner and the light sensitive drum, are housed in a single cartridge which can be replaced in a matter of seconds. In the 4450 this is not the case. Toner is supplied in a plastic bottle, and

PIPEDREAM 3



PipeDream 3 breaks down the barriers between word processor, spreadsheet and database. You can include numerical tables in your letters and reports, add paragraphs to your spreadsheets, and perform calculations within your databases.

Based on PipeDream 2, the best-selling integrated package for the Archimedes, PipeDream 3 has been completely re-written to take full advantage of RISC OS - if you can use RISC OS, you can use PipeDream 3. It is fully multi-tasking and multi-windowing, so you can work on many documents at once and instantly move information between them. And since PipeDream 3 can automatically load and save most popular file formats, including VIEW and First Word Plus, switching to it from other programs has never been easier.

Power, flexibility, speed, ease of use. PipeDream 3. Breaking down the barriers.

For a free brochure, see your Archimedes dealer, or phone us on 0954 211472 or return the coupon.

PipeDream 3 is for all Archimedes computers with RISC OS and 1Mbyte of RAM.

PipeDream 3 costs £147.00 +VAT.

Major features include:

- many documents loaded at once
- intuitive RISC OS user interface
- displaying and printing of pictures within text
- built-in 93,003 word spelling checker
- file compatibility with PC & Z88 PipeDream and BBC View Professional
- background recalculation
- keystroke compatibility with Z88 & PC PipeDream
- Z88 filing system
- automatic loading of VIEW, ViewSheet, Lotus, First Word Plus, Tab and CSV files
- automatic saving of VIEW, Lotus, Acorn DTP format, Tab and CSV files
- multi-field sorting
- use of all available fonts
- 62 spreadsheet functions
- external references for 3-D modelling
- macro file recorder
- slot protection

For a free brochure, complete and return this coupon
PipeDream 3 ☐ View Professional ☐

Name

Address

Post code

Colton Software, Broadway House, 149-151 St. Neots Road, Hardwick, Cambridge CB3 7QJ, England.

Fax: 0954 211607 Tel: 0954 211472

All trademarks acknowledged. The chart in the screen shown above was produced by sending numbers from PipeDream 3 to Langensky's Presenter 2 and then loading the resulting graph back into PipeDream 3.

Colton Software, Broadway House, 149-151 St. Neots Road, Hardwick, Cambridge, CB3 7QJ, England.

Fax. 0954 211607 Tel. 0954 211472

must be carefully shaken into the toner reservoir when the LCD display tells you that a top-up is needed. You must also replace the used toner collection bottle and roller cleaning pad, and clean the fuser and pinch rollers. All the parts needed for this are supplied in the toner pack.

Toner costs around £34 a pack (inc. VAT), and lasts for around 1500 pages (at 5.5% average paper coverage per sheet). This works out at around 2.3p per copy for toner alone. The light sensitive drum should have a life of some 13,000 copies (cost £169 inc. VAT, giving 1.3p per page), and again the LCD display informs of the need to change this. Additionally the developer unit will need changing every 20,000 pages (cost £130 inc. VAT, giving 0.7p per sheet). This takes the cost of consumables to a little over 4p per sheet, apart from the cost of paper.

The advantage of the 4450's approach to these consumables is that because they are only changed when necessary, running costs should be kept down. However, a standard Canon cartridge (as used by the Apple LaserWriter, and other Canon engines), is good for around 3000 copies. It contains all consumables, and costs about £90. This yields a cost per sheet of only 3p, again excluding the cost of paper. Moreover, loading the toner reservoir on the 4450 can be a messy job if you are not very careful.

The 4450 has a first class user interface in the form of an 18 character LCD display and an extensive bank of selection buttons. These permit a vast number of options to be set up by hand, many of which can be permanently stored as defaults if the user so wishes. Some of the cheaper laser printers use more primitive LED displays, with only very limited option selections. In such cases, the information reported back to the user is in the form of an unreadable symbol which must be looked up in the manual. But with the LCD display on the 4450, if

it needs more toner, or a 30,000 page service, it tells you so.

CHARACTER MODE

Connecting the printer to the Archimedes is simplicity itself. The 4450 has both serial and parallel interfaces. The latter uses a standard Centronics connector and provides the most efficient link with the Arc. With the lead connected, you can send data straight to the printer by sending VDU2 (or Ctrl-B) to send the Arc's output through its printer port, and using PRINT statements. Before you do this, you need to set two options from the printer's front panel:

- Set CR to CR - LF (set carriage returns to generate a carriage return line feed sequence)
- Set Emulation mode to Epson

Incidentally, the 4450 has an excellent status printout option (press "Test" then "Enter"), printing out a whole page of status information about the current settings. With the above settings made, you can treat the 4450 as if it were a high quality Epson printer.

You can print out Basic program listings by pressing Ctrl-B, then typing LIST, then Ctrl-L followed by Ctrl-C. When using a laser printer you must remember that you will get no output until the printer receives a whole page (or is given to believe that the page is complete), so if you send less than a page, no paper will emerge from the printer. You can get around this by using Ctrl-L to send a form feed to flush out the final page as in the example above, or contrive to send the correct number of lines to constitute a whole number of pages. Alternatively, you can take the printer off line from the front panel, and click on the "Print" button.

You will see from the timings in figure 2 just how fast the 4450 is in Epson text-printing mode. It prints 11 pages per minute, and each page could contain over

4000 characters. Moreover the first page through only takes 18 seconds, which is a relatively short overhead. Quality, as you can see from the sample in figure 1, is very good. The only proviso here is that the supplied fonts are very limited, and that emboldened characters tend to be a little too heavy.

Character mode (Epson emulation)

First page out	18.7 secs
Each subsequent page	5.5 secs (yielding 11 pages per min)

Graphics mode (LaserJet emulation)

Standard Draw file (150 dpi)	47 secs
Standard Draw file (300 dpi) 3 mins	31 secs
Mode 12 screen (150 dpi)	55 secs
Mode 12 screen (300 dpi) 2 mins	29 secs

Figure 2. KX-P4450 timings for Epson character mode, and LaserJet mode (printing the standard Draw file from Applications 1 disc, and an Archimedes mode 12 screen)

Finally, a word of warning to those using character mode. If you are using the 4450 in conjunction with a word processor, you will need to know the number of characters per line, and the number of lines per page that your printer is set up for. By default you will find that it is (unexpectedly) 65 lines per page, and 76 characters per line (in 12pt Courier). But you can save yourself a lot of time if you test this out first. Also, be careful not to send "Cancel Skip-perforations" codes in Epson mode, since this can result in loss of output at the top of the page.

LASERJET MODE


With Archimedes software which uses the printer drivers, such as Paint, Draw, Impression etc, you will obtain best results by selecting the Panasonic LP emulation mode from the front panel. This emulates the HP LaserJet, and you should install the LaserJet driver on the Desktop. Now, with all output except for ASCII files, the LaserJet driver will prepare a bit image pixel-by-pixel of the required output, and send this to the printer. This will be transferred to the printer's internal RAM, and then, when the whole page is in place, it will be printed.

In LaserJet mode, the user has a choice of output quality. This is selectable from the Arc's printer driver (use Select on the driver icon on the icon bar). Using 150 dpi (dots per inch) gives quite reasonable draft quality at a fair speed, while 300 dpi will give you a very high quality result indeed (see figure 3), but will take more than four times as long (see figure 2). Interestingly, of these two timings, only the last 18 secs or so of each is spent by the laser printer. For the rest of the time, the Arc's printer driver is generating an output image in suitable format.

Apart from its inherent slowness, another problem with the 300 dpi setting is that a page of A4 needs more than half a megabyte of RAM to hold it. Thus if you have a full A4 page of text to be output at 300 dpi, but have not upgraded the 4450's RAM, it will print the first two thirds or so of the page, and flash up an error message. You can then press the "Print" button to print the remainder of the page on a second sheet.

The machine also gives excellent results with halftone graphics, such as digitised pictures or screen dumps. This is partly due to the quality of the printer, which holds its solid blacks very well, and partly due to the printer driver software, and modules such as ColourTrans which are used extensively in translating coloured images to halftones. Of course, laser printers cannot output anything but black dots (albeit very small ones). To create a grey halftone, a suitable dot pattern must be used. This means that definition must inevitably suffer, but if you take a close look at figure 3, you will see just how good the final result can be.

The Panasonic KX-P4450 costs £1499 inc. VAT from BEEBUG.



Text in 14 pt Trinity Medium

ABCDEFGHIJKLMNOPQRSTUVWXYZ 1234567890

Figure 3. The quality of text and graphics output from the 4450 at 300 dpi is excellent

RU

SOLOMON SOFTWARE

FREE DEMO DISK. Just send a blank disk and a S.A.E. for a free demonstration version of the strategy games 'THE CUBE' and 'THE HOUSE OF MIRRORS' and the arcade game 'HOT-PURSUIT'.



OR 'HOT-PURSUIT' a game of cat-and-mouse with a maze to get lost in and dogs snapping at your heels! — £14.95.

Also available 'THE CUBE' and 'HOUSE OF MIRRORS' — £14.95 each.

CHEQUES PAYABLE TO: P. CROALL

Solomon Software,
PO Box 258
Wolverhampton WV2 3AS
Tel: (0902) 28522

A BIGGER, BETTER DIARY for the Archimedes

Choice of three diary sizes.

You can have several active diaries and choose the sizes, up to 15 lines of 40 characters, to suit the task, with more than one year for each task. Easy to use with on-line HELP. The program is fully WIMP based, and multitasks with RISC-OS.

See a full year at a glance.

A single window shows part of the entry for every day of the year. See the free days or spot that elusive entry at a glance. A string search facility enables lost entries to be found.

Instant viewing of the full entry for any day.

Skim the mouse over the year to scan the full entries for any day and just 'click' on a day to make an entry. To-day's entry can be kept on screen for reference.

Print all of a month with just one command.

Select the month, or months, to be printed. Then choose from either a full page formatted print-out, or a quick single line per day, showing only those days which have an entry

£14.95

(incl. VAT & U.K. p.p.)

Cheque or P.O. to

Official Orders also welcome.

QUERCUS COMPUTER SYSTEMS

Courtyard House, North Otterington
Northallerton, N. Yorks. DL7 9EP (tel. 0609 70643)



ROBICO ADVENTURES FOR THE ARCHIMEDES

STRANDED! £29.95

The brilliant new adventure from the leaders in Acorn adventuring!

It is the far distant future and the attractions of inter-galactic travel through the ever-expanding universe have tempted you into stowing away on board a large Starfreighter. The penalties, if caught, are severe ... but surely you have sufficient intelligence and resourcefulness to meet the challenge?

Stranded! It is an enthralling science fiction adventure with over 220 locations, nearly 100 objects and over 130K of text. It features several high resolution colour graphics screens, mouse driven input and an advanced parser. Buy it and you won't be disappointed!

RISE IN CRIME £29.95

Can you rid yourself of the shackles of a conformist, mind-imprisoned society? Mouse driven input, advanced parser, 396K of text, 400 locations, 150 objects and several high resolution graphics screens make this an adventure to remember!

FUGITIVE'S QUEST £29.95

You have been convicted of a murder you did not commit. Can you escape and prove your innocence? 230 locations, 80 objects, an advanced parser, mouse driven input and several full colour, photo-quality illustrations combine to create a must for adventurers!

ENTHAR SEVEN £29.95

Your interplanetary Space Hopper begins to decay. You have to land safely and then explore the planet in order to regain the freedom of the stars. 450 locations, 80 objects, 1200 messages, an advanced parser and some of the best graphics you will ever see make Enthar Seven a true mega-adventure!

Robico Adventures are available from all good computer stores or direct from
ROBICO, 3 FAIRLAND CLOSE, LLANTRISANT, MID GLAM CF7 8QH Tel. (0443) 227354

Please make your cheque payable to 'Robico'
or you may pay using your ACCESS card.



Assembler Workshop

David Spencer takes a close look at register R15.

In this month's assembler workshop we shall take a look at the role of register R15 in ARM instructions. The ARM processor features an *orthogonal* instruction set, which means that R15 can appear in instructions just like any other register. However, as we will see, R15 is unlike the rest of the registers in other respects.

WHAT MAKES A REGISTER?

Unlike the other registers in the ARM processor, R15 is totally dedicated in its use. The register is split into two parts, each with entirely separate functions. The first part, consisting of bits 2-25, makes up the *Program Counter* (PC), while the remaining bits form the *Processor Status Register* (PSR). The PSR is in turn split into six flags, and a two-bit value indicating the processor mode (more of which later). This is shown in figure 1.



Figure 1. The layout of register R15

The program counter is used to hold the address of each ARM instruction being executed. The ARM address bus is twenty six bits wide, and therefore you might expect the program counter to have to be twenty six bits in order to address the full range of memory. However, this is not the case, as the ARM processor insists that all instructions are word aligned. Hence, the two lowest bits of the instruction address will always be 00, and as such don't need to be stored. If you look again at figure 1, you will see that the bits in R15 making up the program counter are offset two bits into the register (in other words, the lowest bit of the PC is in bit 2 of R15). This means that if just the PC bits of R15

are extracted by ANDing the register with &3FFFFFFC, then the result will be the correct address.

PIPELINING

One effect that must always be remembered when considering the contents of the program counter is being *pipelined*. There is not room here to explain this in detail, but its effect is that while a particular instruction is being executed, the address held in the program counter is eight bytes ahead of the address of the instruction itself (or twelve ahead for LDM - see later).

THE PROCESSOR STATUS REGISTER

Before looking at the use of R15 in instructions, we will take a brief look at the flags that make up the PSR. N, Z, C and V are the Negative, Zero, Carry and overflow flags, and are set by the data processing instructions to reflect the status of the result (for instance whether it was zero or not).

The I and F flags are used to disable interrupt requests (IRQ) and fast interrupt requests (FIQ) respectively. More on interrupts can be found in the article *Under the Lid* elsewhere in this issue.

Finally, for the PSR, bits zero and one indicate the current processor mode. This will be explained fully in a future *Assembler Workshop*, but for now it is sufficient to know that these bits are normally 00, indicating the processor is in User Mode. However, while executing operating system routines, such as SWIs, these bits are set to 11 to indicate Supervisor Mode. Further more, these

modes bits themselves, and the I and F flags, cannot be changed in User Mode.

A final point worthy of noting is that R15 is usually referred to in instructions as 'PC', although it does in fact contain both the program counter *and* the status flags.

USING R15 IN INSTRUCTIONS

We can now consider the effects of using register R15 in ARM instructions. There are five basic classes of ARM instruction - data processing, branch, memory transfer, multiple transfer and SWI. We don't need to consider SWI and Branch any further, as although they both alter R15, they do so implicitly.

We will start with the data processing instructions, such as ADD and MOV. The general syntax for these is:

<op> Rd,Rn,Rm

However, for MOV and MVN, Rn is absent, while for the comparison operations (TEQ, TST, CMP and CMN), Rd is not specified.

Rd and Rn can be any ARM registers, while Rm is either an ARM register, optionally shifted or rotated by a constant or further register, or an immediate value. We are interested in the case where R15 is used for any of Rd, Rn and Rm.

The rules the ARM employs in these cases are simple. If Rm is R15, then all thirty-two bits of the register are used, in other words both the PC and PSR. On the other hand, if Rd is R15, then only the PC bits are used, and the PSR bits are seen as zeros by the instruction. For example,

MOV R0,PC

will copy *all* of R15 into R0, while,

ADD R0,PC,#0

will leave R0 containing just the PC bits from R15. In both cases, the PC will be eight bytes ahead of the instruction address, because of pipelining.

The effect when Rd is R15 depends on whether the 'S' flag is present in the instruction. Normally, this flag is used to reflect the result of an arithmetic operation in the PSR flags. However, when the destination register is R15, the S flag determines whether all of R15 is updated (with S present), or just the program counter bits (without the S). For example, the instruction:

MOV PC,R14

will 'jump' to the address in R14, leaving the flags unchanged, while:

MOVS PC,R14

will perform the same jump, but will replace the flags with the corresponding bits in R14.

One instance where using R15 in an ADD instruction is very useful, is when jumping to one of a set of routines depending on the contents of a register. This can be realised using the following code:

```
CMP    R0,#entries
ADDCC  PC,PC,R0,ASL #2
B      outofrange
B      option0      ;x
B      option1
B      option2
etc.
```

Assuming that R0 contains the number of the routine to call, starting at zero, the first instruction checks that it is in the correct range (where *entries* is the number of table entries). Assuming it is alright, the ADD instruction will add the entry number times four to the program counter, which at this time points to the instruction labelled x. It should be easy to see that this will skip to the appropriate branch instruction which in turn jumps to the actual routine. If the value was out of range, then the branch after the ADD is executed instead. Such code is frequently used to dispatch SWI calls within a module.

The comparison operations (TEQ etc.) have a final trick up their sleeves. Normally, these instructions use the

flags to reflect their result. For example, TEQ will set the Z flag if the two arguments are equal. However, if the instruction is followed by a 'P', the effect is changed so that the result of the operation (which is normally discarded) is written directly to the PSR flags, without affecting the program counter. To understand this, consider the following:

```
MOV    R0, PC
ORR    R0, R0, #1<<29
TEQF   R0, #0
```

The first instruction copies all of R15 (PC and PSR) to R0. The ORR instruction then sets what was the carry flag. To understand what happens next, we need to understand how TEQ works. This instruction performs a comparison by Exclusive ORing its two arguments. If they were equal, the result will be zero, and the Z flag will be set. The result itself is normally discarded. However, as stated above, the 'P' modifies the operation so that the Exclusive ORing is still performed, but the result is written directly into the PSR flags of R15 on a bit by bit basis. The net effect of this is that all the flags will be rewritten with their original values, except for the carry flag which will be forcibly set as a result of the ORR instruction.

Moving on to the load and store instructions, LDR and STR, these can use R15 as the register being transferred, the base register, or the offset register. The only useful form is when R15 is the base register, for example:

```
LDR    R0, [PC, #100]
```

This allows a transfer of data from an address that is relative to the current instruction. Such an operation is called a *program relative transfer*. In practice, a simpler form of instruction is used, for example:

```
LDR    R0, data
```

where *data* is a label elsewhere in the program. The assembler will translate this into an appropriate instruction of the

form given above, automatically taking into account the effects of pipelining.

The final class of instructions consists of the multiple load and store operations - LDM and STM. These take the general form of:

```
LDM/STM Rb[!], {reg list} [^]
```

where *reg list* is a list of ARM registers, and the ! and ^ qualifiers are optional. The base register, Rb, cannot usefully be R15, as the ARM uses all thirty-two bits. This means that unless all the flags are reset, the interrupts are enabled, and the processor is in user mode, an address exception would occur. R15 can however appear in the register list. In the case of STM, all thirty-two bits of R15 will be saved. However, because of the effect of pipelining, the program counter that is saved points twelve bytes ahead of the STM instruction itself. In general, STM instructions that save R15 are not used a great deal. On the other hand, loading R15 with an LDM instruction can be very handy. The main use is to return from a subroutine, where the return address is saved at the start using:

```
STMFD R13!, {R14}
```

and a return from the subroutine is performed using:

```
LDMFD R13!, {PC}
```

This has the effect of reloading the program counter with the value on the stack, leaving the status flags unchanged. If the optional '^' is used with the instruction, then not only is the program counter loaded, but also the flags. This is very useful for restoring the flags to the state that they were at the start of a subroutine.

CONCLUSION

While the orthogonality of the ARM instruction set allows R15 to be used in almost any instruction, the main uses are those described above. Understanding the possibilities of using R15 can, however, often allow more elegant and efficient code to be written.

RU

INVESTIGATOR 1.02

£24.95

THE SERIAL PORT



Investigator is a disc utility program which is compatible with the Archimedes 300, 400 and 3000 series using either the Risc OS or Arthur 1.2 operating systems.

Investigator can perform the following operations on discs of many different formats:

- Examine the format of the disc in detail.
- Edit the data stored on the disc.
- Make backup copies of the disc.
- Store the entire disc as an ordinary ADFS file. This may allow archives of several master discs to be stored on a single backup disc. The disc may then be transmitted to a remote site using a modem and a communications package such as ARCterm.
- Fully WIMP front end.

The Serial Port, Burcott Manor, Nr Wells, Somerset BA5 1NH
Voice (0749) 72234 Data (0749) 79794 (300-2400 baud)

Please send me ☐ INVESTIGATOR 1.02 at £24.95, cheque, PO enclosed.
☐ Data Sheet

Name _____

Address _____

Probing Pascal

David Spencer gives a brief overview of the Pascal language, and takes a look at the two compilers available for the Archimedes.

To some people Pascal is the ideal programming language, while others see it as little more than a toy. To understand these opposing views we need to look at the nature of Pascal. When the language was first developed in the late sixties, the main languages in use were Fortran and Basic, both of which lent themselves more to spaghetti programming than the doctrines of structured programming which were emerging. Pascal's inventor, Niklaus Wirth, recognised that there was a need for a language which could be used to implement algorithms directly, without getting bogged down in the pragmatics of that particular language. With this in mind, Wirth invented Pascal as a highly structured, totally machine-independent, language.

With its features of machine independence and closeness to theoretical algorithms, Pascal makes an excellent teaching language. For this reason, Pascal tends to be loved by academics, but frowned upon by real-life programmers who see it as too 'simple' to cope with the needs of practical applications.

STANDARD PASCAL

A few years ago, a standard version of Pascal was defined in an attempt to improve portability, much as with C today. This definition is known as ISO7185 in America, and BS6192:1982 in this country. Unfortunately, the standard only defines a minimal version of the language, and most real compilers add numerous extensions, immediately defeating the object of a standard. As an example of this, the file handling defined in the standard doesn't provide a very satisfactory way of accessing actual files on disc. Instead, files are thought of as temporary entities that exist only for the duration of execution, and even then only sequential access is possible. Needless to say, file handling is one of the areas in

which all Pascal compilers offer some extensions.

There are in fact two levels to the standard. Level 0 is the basic definition, while level 1 adds an extra concept known as a Conformat Array Parameter (CAP). This is a special mechanism that allows functions to be written that can take arbitrary sized arrays as parameters. Without CAPs, the syntax checking is so rigid that the dimensions of each array parameter must be specified at compile-time.

COMPILERS

There are currently two Pascal compilers for the Archimedes. The first of these is the official Acorn ISO-Pascal, which is now in its second version, and the other is the new Cambridge Pascal from Dabs Press.

Both of the compilers support the BS6192 standard version of the language, although only the Acorn one features the optional CAPs. Both compilers also offer similar extensions, mainly to deal with string handling, graphics and operating system calls. Cambridge Pascal has the additional feature that it can be used to compile relocatable modules, allowing new star commands to be written in Pascal. ISO Pascal, on the other hand, compiles into Acorn Object Format (AOF) which means that a program can include routines written in ARM Assembler or C. However, there are a few problems with this, all of which are detailed in the user guide.

USING THE COMPILERS

In use, the two compilers are quite different. ISO-Pascal is entirely command-line driven. This means that each time you want to compile a program you must exit to the command-line prompt, compile the program, and then link it with the

Pascal library to obtain an executable program. As the compiler, linker and library have to be loaded off disc each time, this can be quite time-consuming.

Compiler	Compilation Time	Execution Time	Length
ISO Pascal	30s	3s	33K
Camb.Pascal	2s	5s	1464 bytes*
* Plus 17K for library module			

Table 1. Timing for Sieve of Eratosthenes for all primes up to 7000.

Cambridge Pascal, on the other hand, exists as a relocatable module and can be run from the Desktop. All you need to do to compile a program is drag the source file to the compiler icon on the icon bar, drag the object file icon to wherever you want the code to be saved, and sit back while the compilation takes place. This process is, however, not multi-tasking; instead, the compilation takes place in a command window, with all other tasks suspended. The resulting object code is also shorter than that produced by ISO-Pascal, as they make use of a module-based library which is loaded in at the same time as the compiler. A dialogue box allows the various compiler options to be changed, and finally, you can still run the compiler from the command-line if desired.

One problem with the Cambridge Pascal setup is the amount of memory used. As it is loaded as a module, memory is used for this, as well as the library module. This takes up about 225K of memory which cannot easily be recovered without a hard reset once it has been claimed. As ISO Pascal is loaded from disc each time, it only takes up memory when actually in use.

PERFORMANCE

Table 1 gives timing for compilation and execution of a sample program with both compilers. Each system offers a number of 'speed-up' options, such as disabling Escape checking during execution. For the purposes of these timings, both compilers were set up to offer the same features. You can see that Cambridge Pascal is much faster at compiling, but slower at execution than ISO Pascal.

DOCUMENTATION

Cambridge Pascal is supplied with a 58 page user guide, while ISO Pascal has two user guides - a main one of 136 pages and a 34 page update. The manuals for both systems document the use of the compiler, the extensions and the various error messages and warnings. Despite its greater length, I found the Acorn manual rather terse, and it always seemed to stop short of explaining any subject fully. It can also be very confusing always to have to cross reference the update guide for any additional information.

Cambridge Pascal also includes a large number of example programs on the disc, while ISO Pascal just has the obligatory 'Hello World' program. Not only do these programs give you something with which to get started, but they also illustrate all the extensions of the language.

Neither compiler includes any details on programming in Pascal. However, this is not a problem, as the widespread use of Pascal in teaching ensures that a visit to any computer bookshop will reveal a plethora of suitable tutorial guides.

CONCLUSION

Despite the features offered by both compilers, I can't see many people using Pascal for serious software development. Instead, I think the people most likely to use Pascal on an Archimedes are students, for whom the language frequently makes up the bulk of first-year programming courses. Therefore, I feel that the prime qualities that these compilers will be judged on are ease of use, and adherence to the ANSI standard, although some extensions are important,

such as those for file and string handling. Cambridge Pascal has to win on ease of use, as programs can be edited, compiled and executed without leaving the Desktop. On the other hand, ISO Pascal pips its rival at the post on ANSI compatibility, as it supports the full level 1 standard. The other consideration is of course cost, and with Cambridge Pascal over £30 cheaper than Acorn ISO Pascal, the Dabs Press product has to come out the overall winner in my view.

Product ISO Pascal
Supplier Acorn Computers Ltd.,
 Fulbourn Road,
 Cherry Hinton,
 Cambridge CB1 4JN.
 Tel. (0223) 245200
Price £113.79 (inc. VAT)

Product Cambridge Pascal
Supplier Dabs Press, 5 Victoria Lane,
 Whitefield,
 Manchester M25 6AL.
 Tel. 061-766 8423
Price £79.95 (inc. VAT)

RU

INVOICING & ACCOUNTS

New: V3 of The Account Book now available. Comprehensive small business accounts to trial balance. VAT approved. Absolutely the easiest program to use, with neat final books and hundreds of reports. No entry limits. "The Account Book gets first prize for both price and performance" - comparison in Micro User-July '89. A true user-friendly program. It succeeds admirably "Beebug - Oct '88. And that was Version 2, V3 has many new features. £27.95.

New: V2 The Invoice Program. The magazines haven't had a chance to review this yet, but our customers have, and they love it. Database, Invoices (unpaid and paid), Statements (individual and automatic), Stock presets, Debtor lists, Linking with The Account Book and loads more £27.95.

Special Offer: £49.95 if purchased together.

Apricote Studios

2 Purle Bridge Farm
 Manea
 Cambs
 PE15 0ND

Tel: 035 478 432 for information, help or to order.

New Outline Fonts for Archimedes

Fonts fonts fonts fonts

Fonts fonts fonts fonts

Fonts fonts fonts fonts

Fonts fonts fonts fonts

Fonts fonts fonts fonts

Fonts fonts fonts fonts

Fonts fonts fonts fonts

Suitable for any Archimedes software requiring new high quality Outline Fonts from:



We are making an amazing introductory offer:

Typefaces from	£1.99
Acorn Desk Top Publisher	£125.00
Acorn D. T. P. with 40 fonts	£159.00
Canon Bubble Jet printer (360 d.p.i.)	£529.00

For comprehensive Font Catalogue please write to:

ELECTRONIC FONT FOUNDRY

18 Brockenhurst Road • Ascot • Berkshire SL5 9DL

A Check Save Module

Peter Arnold describes a short utility which can prove invaluable in preventing the accidental overwriting of files.

The short module listed here provides a useful function, particularly for program developers, but others as well. Whenever a save function is to be performed, the utility, once installed, checks to see if any file with the same name (and pathname) already exists, and if so seeks confirmation from the user before proceeding. This can be invaluable for preventing the inadvertent overwriting of files, whether saved directly (from within Basic or from the command line, for example), or from the Desktop (by dragging). In the latter case, pressing the Select button confirms ('Y'), while any other button cancels.

The utility is supplied in the form of a module called *RMCheck*, which can be assembled by entering and running the program listed here (but do save the source code before running it). It would also be advisable to save a copy of the original program once entered (use the name *CheckSave*) in case any mistakes have occurred. Once the module has been created, it can be installed by double clicking on its icon in a directory viewer, or by typing:

```
*RMLoad RMCheck
```

in response to the system prompt (*).

Once loaded, the module is immediately active. However, two star commands have also been provided, **CheckOff* and **CheckOn* which may be used to switch the check off, or back on again. The module will also respond to the use of the **HELP* command followed by the module name, e.g.:

```
*HELP RMCheck
```

This module is particularly useful to anyone developing programs in Basic, but also in any situation where it is otherwise

possible to overwrite a file without realising what has happened until maybe too late.

For those who may be interested in the workings of the program, an annotated version is included on the magazine disc.

```
10 REM >CheckSave
20 REM Program Save Checker
30 REM Version A 1.0
40 REM Author Peter Arnold
50 REM RISC User Jan/Feb 1990
60 REM Program Subject to Copyright
70 :
80 DIM code% 1000
90 PROCassemble
100 OSCLI"SAVE RMCheck "+STR$(code%)+
"+STR$(P%)
110 OSCLI"SETTYPE RMCheck FFA"
120 END
130 :
140 DEF PROCassemble
150 FOR pass%=4 TO 7 STEP 3
160 P%=0:O%=code%
170 [OPT pass%
180 .Start
190 EQU0 0:EQU0 Init
200 EQU0 ReleaseVector
210 EQU0 Service:EQU0 Title
220 EQU0 Help:EQU0 Comms
230 .Title
240 EQU0 "CheckSave"
250 EQU0 0:ALIGN
260 .Help
270 EQU0 "Save Checker"+CHR$(9)+"1.00 ("
+MID$(TIME$,5,11)+")"
280 EQU0 0:ALIGN
290 .Comms
300 EQU0 "CheckOn":EQU0 0
310 ALIGN:EQU0 Checkon:EQU0 0
320 EQU0 Onsyn:EQU0 Onhlp
330 EQU0 "CheckOff":EQU0 0
340 ALIGN:EQU0 Checkoff:EQU0 0
```

Check Save Utility

```

350 EQU D Offsyn:EQU D Offhlp
360 EQU B 0
370 .Onhlp
380 EQU S "CheckOn turns on save checki
ng"
390 EQU B 13
400 .Onsyn
410 EQU S "Syntax: *CheckOn"
420 EQU B 0
430 .Offhlp
440 EQU S "CheckOff turns off save chec
king"
450 EQU B 13
460 .Offsyn
470 EQU S "Syntax: *CheckOff"
480 EQU B 0
490 .Checkon
500 LDR R12, [R12]:MOV R0, #1
510 STR R0, [R12]:MOV PC, R14
520 .Checkoff
530 LDR R12, [R12]:MOV R0, #0
540 STR R0, [R12]:MOV PC, R14
550 .Service
560 STMFD R13!, {R14}
570 CMP R1, #427
580 BLEQ ClaimVector
590 LDMFD R13!, {PC}
600 .Init
610 STMFD R13!, {R14}
620 MOV R0, #6:MOV R3, #1
630 SWI "OS_Module"
640 STR R3, [R2]:STR R2, [R12]
650 BL ClaimVector
660 LDMFD R13!, {PC}
670 .ClaimVector
680 STMFD R13!, {R0-R3, R14}
690 MOV R0, #8:ADR R1, CodeStart
700 LDR R2, [R12]:SWI "OS_Claim"
710 LDMFD R13!, {R0-R3, PC}
720 .ReleaseVector
730 STMFD R13!, {R14}
740 MOV R0, #8:ADR R1, CodeStart
750 LDR R2, [R12]:SWI "OS_Release"
760 LDMFD R13!, {PC}
770 .CodeStart
780 STMFD R13!, {R0-R12, R14}
790 LDR R6, [R12]:CMP R6, #1
800 BNE Exit

810 CMP R0, #0:CMPNE R0, #10
820 BNE Exit
830 MOV R0, #5
840 SWI "XOS_File"
850 CMP R0, #0:BEQ Exit
860 MOV R9, R1:SWI "OS_WriteS"
870 EQU S "File exists - Overwrite (Y/N
) ?"
880 EQU B 7:EQU B 0:ALIGN
890 BL Entry
900 .Access
910 AND R1, R5, #8:AND R2, R5, #2
920 ORR R1, R1, R2:CMP R1, #2
930 BEQ Exit
940 SWI "OS_WriteS"
950 EQU S "Insufficient access - Contin
ue? (Y/N)"
960 EQU B 7:EQU B 0:ALIGN
970 BL Entry
980 MOV R1, R9:MOV R0, #4
990 MOV R5, #51:SWI "OS_File"
1000 .Exit
1010 LDMFD R13!, {R0-R12, PC}^
1020 .Nosave
1030 SWI "OS_WriteS"
1040 EQU S "Save abandoned"
1050 EQU B 0:ALIGN
1060 SWI "OS_NewLine"
1070 LDMFD R13!, {R0-R12, R14}
1080 LDMFD R13!, {PC}
1090 .Entry
1100 MOV R7, R14:SWI "OS_Confirm"
1110 SWI "OS_WriteC":SWI &10D:SWI &10A
1120 BCS Nosave:BNE Nosave:MOV PC, R7
1130 ]:NEXT
1140 ENDPROC

```

RU

Multitasking Link Archimedes - BBC

List BBC files in a directory viewer Drag files to
directories and applications.
Software only £9 inc p&p
Software + lead £20 inc p&p

Ivoryash Ltd, 14 Perwell Close, Bredon,
Tewkesbury Glos, GL20 7LJ.

Hyperbook

Reviewed by Mark Sealey

INTRODUCTION

Hyperbook is the result of the collaboration between the world's fifth largest book publisher and one of the most successful BBC/Acorn software houses. Longman, in fact, has recently merged its software division with the "serious" (i.e. non-games) side of Logotron. This product is one of the first to appear since the merger.

Hyperbook is a text retrieval system which will have appeal far beyond the educational market (for which Logotron is best known), and the software also runs on the RM Nimbus and on PCs and compatibles. As a package, Hyperbook consists of two components: the *reader*, and the text files on which this works. To date files in social, religious, historical, geographical, economic, environmental, scientific, literary and political fields have already become available.

The ten titles which make up this output are reasonably priced and cover a range of (mostly topical) interests. Given the amount of data, which is stored in compressed format - typically 320 screen 'pages' on one 800K disc - these represent good value for money.

USING HYPERBOOK

Because this first version of the software necessarily has one eye on compatibility with other hardware systems, there are no concessions to the RISC OS Desktop, although a Wimp system of sorts is employed. Menus are pulled down from the top of the screen, most of the rest of which is occupied by the text.

These menus concern Filing, Glossaries, Vocabulary, Output and the ubiquitous Miscellaneous, as well as one other of some importance, Indexes. The documentation is clear, easy to follow and

unambiguous, guiding the user around all of these facilities.

Two functions require a little explanation. As well as being able simply to read text, print it, spool it to a word processor or just browse with all the usual cursor key and Page Up/Down conventions, you can compile, edit, save and load so-called *glossaries* which augment the basic text.

In similar vein, *vocabularies* are used to search a range of pages within a text for a variety of purposes, notably to draw a user's attention to just those unfamiliar words which you might want to deal with later in a glossary. Each glossary entry is limited to a maximum of 90 characters.

These functions are typical of the well thought-out and logical design of Hyperbook, which is also reflected in the menu system.

INDEXES

Hyperbook, then, can scan text, provide lexical information, and print out either, (and if necessary allow access to the operating system). Most of this mirrors more or less what would happen if you were using a printed book and moving backwards and forwards through its text in a conventional manner.

Hyperbook's main claim to fame lies in a very substantial extra feature to normal text use: the *Index*. It is harder to describe how the Hyperbook index system works than it is to use it.

A Hyperbook index is essentially different from that of a printed book in that it is not necessarily linear. Even the most well-indexed reference book could scarcely pick out every occurrence of every word, but Hyperbook can.

More usefully, though, imagine a hypothetical text file published on the general subject of microcomputers and loaded into Hyperbook. Every instance of the word 'computer' could effectively be tagged. Hyperbook "multi-tasks" internally with its other activities so that, as soon as one instance of 'computer' is found, it can be located, highlighted on screen and examined in context while the search continues. Other Hyperbook operations (including up to three other searches) can also proceed at the same time with little noticeable slowdown in performance.

By simple use of the cursor, a second and perhaps more specific sub-index can be generated at one level down from the earlier one on 'computer'. This might find every mention of 'Acorn' or of 'BBC'. Selection criteria are essentially Boolean, and permit wildcards too. There can be up to six 'sub-indexes' from each parent.

Conceptually, this second search is located below the catch-all 'computer' one from the user's point of view. This can be enormously useful as it effectively follows the user's thought processes and allows layers of sub-indexes to be created.

Hyperbook has a neat way of determining where a reference begins and ends. The software controls the amount of text (in practice this is likely to be the number of lines) which gets printed either side of the target words. This *extent* setting can be controlled by the user. Typically it will be a number of lines (default +/- 3) either side. But it could be the whole page (maximum) or the minimum of just the line in question.

The same facility can set the extent after one reference is found before a following one is considered as a separate item. This means that texts containing highly repetitive material or lists can be made more manageable.

There are currently ten titles in the catalogue and as many again scheduled

for early 1990. The content of the *Economics, Social and Geographical Issues* discs is necessarily selective. Like the 20th Century History release, they provide an encyclopaedic source for exploration and reference, rather than continuous, sequential reading.

Also available is the *Authoring System* (£17.25 inc. VAT); this allows text from any source (a variety of word processors, for example) to be converted into Hyperbook format.

CONCLUSIONS

Hyperbook is an excellent product, excellently produced. By the side of the relative sophistication and colourful screens of RISC OS, some will say it is a little low-key. In fact, its appeal is none the less for that. It does everything claimed of it well, and is very reasonably priced. Assuming worthwhile titles continue to appear in quantity, it ought to set a new trend in software for the Archimedes.

Product Hyperbook
Supplier Longman/Logotron,
Dales Brewery,
Gwydir Street,
Cambridge CB1 2LJ.
Tel. (0223) 323656

Prices £56.35 inc. VAT for the Reader,
£17.25 to £27.50 inc. VAT for text files,
£5.75 inc VAT for a demonstration
Green disc.

RU

DVS PUBLIC DOMAIN

All discs have lots of extras

- #1. Logo Sprite Edge Detector, 167 World Flags, Interactive Clares Wire Frame City, Buynones, Trendy Scroller, Mandelbrots, Graphics Quizzes.
- #2. Garfield, O&X's, Nim Game, Battleships, PRESTEL Tasker, 30 Maestro Tunes, Metric Converter, Car Race, Calendar Print.
- #3. Hangman, Connect Four, CD Quality Smooth Criminal, 2 Screen Compactors, Sprite Masking Utility, VDU test.
- #4. 3D Turning Skull, Breakout, Zap Revolving Graphics, Arcade Pairs Game, File Compare Util, Text Dumper.
- #5. Simple Simon, Gold Touch Graphics, Snake Game, More Maestros, 3d Edit, Buynones 2, Planet Info, Key Board Test.
- #6. Fast Neon Sign Writer, MicroMessages Scrolling Package, CHRS editor, STD code finder/sort, Card Sharks, Graphics Quizzes.

£2 Each or £11 for all Six

Cheques to DVS Public Domain

10 Ravenhurst Drive, Birmingham, B43 7RS

TECHSOFT

DESIGNER intro

POSSIBLY THE ONLY DRAUGHTING SYSTEM YOU WILL EVER NEED

Created specifically for the Archimedes, **DESIGNER INTRO** is based on its big brother **DESIGNER (ARCHIMEDES)**. It shares the same uniquely logical menu structure and many of the powerful draughting routines. Enough power in fact to cope with all of most peoples draughting requirements. Many of **INTRO**'s features are shown below. There is one feature however that we cannot show - its most important one - the simplicity of use that guarantees a short learning curve and speedy drawing generation.

FEATURES

Fully menu driven with simple prompts and instructions for all routines.

User definable grid with grid lock. Hunt and lock onto nearest end of line, arc or centre of a circle with a single button press.

True arcs, tangents and normals, essentials for most drawing applications but particularly important for engineering applications. Nine in-built arc types alone.

Ellipses, full or part.

Powerful delete facilities, e.g., last item, line, part, line, arc, part arc, etc. (The software automatically finds intersections.)

Unique **MODIFY** command allows drawing to be redrawn a line at a time forwards or backwards. The drawing may be 'entered' at any point thus giving total flexibility to edit and alter drawings.

Automatic or manual dimensioning, user definable arrow heads/leader lines.

Text entry at any size, angle or slope. (Text output limited only by the plotter available.)

Hatching at any angle/spacing. Automatically finds enclosed boundary plus single or multiple islands.

Powerful **ELEMENT** (layer) structure.

No practical limit to the number of drawing elements that may be created.

Comprehensive transformation commands: **MOVE**, **ROTATE**, **MIRROR**, **IMAGE**, **ALTER SIZE**.

No practical limit to the size of drawing created - limited only by disk space.

Libraries of drawings can easily be created. Library items can then be incorporated into the current drawing at any size, angle, position. Zoom, scale and pan facilities (plot-outs may be taken at any time).

Output to wide range of line plotters from A5 to A0, e.g., Graphictek, Hewlett Packard, Hitachi, Plotmate, Roland, etc. Plus screen dumps for FX/MX/RX compatible printers.

COST EFFECTIVE CAD FOR YOUR ARCHIMEDES

In creating **INTRO** TechSoft have kept the features that made **DESIGNER (BBC)** so popular. There is however one feature that we have cut back on - the cost. **INTRO** is not a toy (although you will enjoy playing with it), it is a true working system at a realistic price.


P.S. If your draughting requirements are more demanding than normal take a look at **DESIGNER (ARCHIMEDES)**, more than a match for any drawing.

PERIPHERALS

Please remember that TechSoft can supply a wide range of CAD related peripherals and accessories, e.g., plotters, plotter pens, etc.

ORDERING

Cheque with order please, payable to TechSoft UK Ltd.
Add VAT @ 15% of total. (Official educational orders welcome.)



COST EFFECTIVE CAD

ONLY **£75** + VAT.
(OVERSEAS **£95**)

TECHSOFT
NEW IDEAS IN SOFTWARE

TechSoft UK Ltd
Old School Lane
Ernrys, MOLD
Clwyd CH7 4DA
Tel: 082 43 318

Mastering the Wimp

Part 5 - Responding to Redraw Requests

by Lee Calcraft

In the series so far we have looked at the way in which Wimp_Poll maintains a dialogue with each active task. When the Wimp_Poll returns a reason code of 2 this constitutes a request by the Wimp to open (or re-open) a particular window. This occurs when the adjust size icon or the title bar icon of a window are selected, or when scroll bars are dragged to a new position.

The usual way for the task to respond to this is to call SYS Wimp_OpenWindow (SWI &400C5), just as we have done in line 450 of our test program from part 1 of the series. This puts the onus back on the Wimp to manage any redrawing of the window which is necessary.

The form of the parameter block returned by the Wimp to accompany a reason code of 2 was given in figure 1 of last month's article. It is exactly the form required when making the Wimp_OpenWindow call, so no data whatsoever needs to be set up by our task. We do not even need to insert the window handle at block% as we have done in our test program - even this is performed for us by the Wimp when it returns a reason code of 2.

In response to our call to Wimp_OpenWindow, the Wimp will begin the business of opening (or re-opening) the nominated window. During this process it checks window flag 4 (see figure 2 from part 3 of the series) - *window needs no help from the task in redrawing the window* - and if this is set, it puts the window on screen. Many windows however, will have bit 4 unset, meaning that the task must be invoked to draw text or graphics in the window.

In such cases (and also when another window uncovers a part of the task's window), the Wimp will return a reason code of 1 (redraw window request) to the

task next time around. The task must respond to this in a very special way. It is no good for example for the task to respond by directly drawing text or graphics onto the screen: the window in question might well be partly (or even fully) obscured by another.

Our example program responds to reason code 1 by calling PROCredraw. The Wimp_Poll loop thus takes the form:

```
DEFPROCpoll
SYS "Wimp_Poll",,block% TO reason%
CASE reason% OF
    WHEN 1:PROCredraw
    WHEN 2:SYS"Wimp_OpenWindow",,block%
etc.
```

PROCredraw takes a very special form, as you can see if you take a look at the listing below. It first calls Wimp_RedrawWindow (SWI &400C8), and then repeatedly calls SYS Wimp_GetRectangle (SWI &400CA) until the Wimp says that it has had enough (more% becomes zero).

```
790 DEFPROCredraw
800 REM Redraw Window
810 SYS "Wimp_RedrawWindow",,block% TO
more%
820 PROCgetorigin(block%,x0%,y0%)
830 WHILE more%
840   PROCdraw(x0%,y0%)
850   SYS "Wimp_GetRectangle",,block%
TO more%
860 ENDWHILE
870 ENDPROC
```

What is going on here is that in the first place the task tells the Wimp that it is ready to get on with the job of redrawing (as prompted by the reason code of 1 returned at the last poll by the Wimp). The Wimp then decides upon which parts of the window need redrawing. If the window is uncovered,

then this could be the whole window, but if it is partially covered by other windows, then this could be a series of rectangles which, taken together, add up to the total

area on display (see figure 1).




Figure 1. Window Updating. If the Wimp needs to update TASK 1, it will split the area into rectangles A and B, and request in turn that the two be updated.

cursor). Finally it fills the parameter block, and returns the task a flag indicating that there is an area to be updated.

The task in its turn redraws that area with whatever text or graphics it requires, and then calls `Wimp_GetRectangle`, which sets up the next rectangle in the sequence. This continues (with a whole series of calls to `Wimp_GetRectangle`) until the Wimp has updated all the rectangles in the task window which had become invalid, and the job is complete. If you look carefully as you use the Desktop you will see this process in action. The Wimp updates each semi-obscured window bit-by-bit.

In practice, a task can respond in two different ways to the parameter block returned. The simplest way is to redraw everything in the whole of the task's work area each time that any rectangle is requested. This relies on the clipping window to ensure that only those parts of

the window which the Wimp requires will actually be drawn on screen. Of course, if you have a very large work area (as you might with a text editor full of text for example) this approach would be impossibly slow, since the task would need to write the whole text file to the screen every time that the Wimp needed to update even a square centimetre. A much more efficient (and more complex) approach is for the task to narrow down the contents of the work area as closely as possible to that needed for redrawing the segment of window which the Wimp is updating, and draw this only, bearing in mind of course, that if you are dealing with sprites, it is not feasible to split them. For the sake of (relative) simplicity, we will stick with the former approach, referring those interested in the latter to the PRM.

Our test program then, adopts the simple approach. It uses `PROCgetorigin` to work out exactly where on the screen our window is to be displayed, and then every time that the Wimp asks for a segment of it to be redrawn, it redraws the lot using `PROCdraw`, relying on the clipping window set up by the Wimp to ensure that only the nominated rectangle is updated each time.

Working out the origin for the redraw is performed very simply in lines 900 and 910 of the program, but explaining the calculation is a little less simple. Take a look at figure 2. This shows the relationship between visible area, work area and scroll offsets. Essentially, the Wimp parameter block available to us contains the visible area minimum and maximum x and y co-ordinates, and the scroll offsets (as well as information on the co-ordinates of the rectangle within the window which needs updating - but which we will ignore), and we need to calculate the work area minimum x and y co-ordinates in terms of the graphics origin. Getting the x co-ordinate is easy, we just subtract the scroll offset from the

visible area minimum x co-ordinate. For the vertical dimension we take the *maximum* visible area y co-ordinate and subtract the vertical scroll offset (which itself is measured downwards, and will therefore be negative).




Figure 2. Calculating the origin for window redrawing

With this under our belt we can go about the business of writing to our window. In the example program from part 1, the time and date were written in the window, and a small filled circle drawn. This was accomplished in PROCdraw, defined as follows:

```
940 DEFPROCdraw(x0%,y0%)
950 SYS "Wimp_SetColour",11
960 MOVE x0%,y0%-40
970 PRINT TIME$
980 SYS "Wimp_SetColour",10
990 CIRCLE FILL x0%+100,y0%-400,50
1000 ENDPROC
```

x0% and y0% are the co-ordinates of the origin of the work area, expressed relative to the graphics origin as described above. They refer to the top left-hand corner of the work area.

The calls made to SYS Wimp_SetColour serve to define the

current graphics colour. We cannot simply use GCOL for this purpose because this would give a colour dependent upon the currently set mode - and multi-tasking programs should wherever possible work in all modes. The parameter supplied with the call is simply the colour number (0-15) in the Wimp palette. To get an idea of the range of colours available, take a close look at the Desktop palette icon. This contains all 16 colours displayed in numerical order from 0 at the top left to 15 at the bottom right.

The time and date are displayed in our window using the PRINT TIME\$ statement in line 970, and since VDU 5 is operative, we must move the graphics cursor to the position on screen where the text is to start - hence the preceding MOVE

x0%,y0%-40 statement. Note the way we have *subtracted* 40 from the y co-ordinate to place the text 40 graphics units *below* the top of the work area. A similar approach is adopted for drawing the circle, but here an offset of 400 graphics units is used to place the graphic well below the text.

At this point it will be worth experimenting with PROCdraw. Try altering the colours and positions of the items, and writing your own text. If you replace TIME\$ with a piece of text of forty or more characters in length you will discover that the right-hand end of it is irretrievably lost. Although the window will scroll to the right, it will not scroll far enough for the end of the text to be visible, and text does not automatically drop down on to the next line as it does when printing on a normal screen or in a text window (with VDU4 active).




Figure 3. Text which extends beyond the edge of the work area is truncated

In other words, if you are using the Wimp, you cannot get text on to the screen by simply executing a series of PRINT statements. You need to go about the whole process with a great deal of care. Each PRINT statement must be preceded by a MOVE statement, and the length of each line of text must be less than the width of the work area.


Moreover, if you have an application which generates some text as its output, you cannot always PRINT this to the screen the moment that the information becomes available, because you must have a way to refresh as much of the screen as the Wimp requires *whenever* the Wimp requests it. Thus if you are writing a Cross Referencer say, which displays the names of functions and procedures in a program file which has been dragged to it, you must actually write your findings to a buffer area in RAM within the task program rather than printing them in the first instance; and then implement a routine to display the contents of the buffer whenever a redraw request is received. The point being that you cannot implement a new search (for procedures etc.) *each time* the Wimp needs to redraw the display. This problem will of course occur in many different kinds of applications, and its resolution will add a level of complexity to all such programs.

Although we have filled our allocated space this month, we have not quite finished the theme of window redrawing. Next month we will look at how to force a window to be updated in order to display new information.

RU

Emerald Publishing

Acorn dtp



An advanced user guide
by
Anne Rooney

The advanced user guide helps you get the most from Acorn DTP. With full operating instructions, hints and tips, style guidelines, instructions on creating a wide variety of documents, and on how to exploit its powerful features to the full, this book leads you through ownership of Acorn DTP from installation to becoming an expert user. It goes far beyond the official User Guide.

Available now from Emerald Publishing, Dept R, PO Box 324, Cambridge CB1 3HB, £14.95; examples disk, £3.95, p&p included. Cheques payable to Emerald Publishing.

David Spencer concludes his look at the Archimedes' hardware.

So far in this series, we have looked at the ARM processor itself, the memory, and the video and sound systems. The one major area we have yet to examine is the peripheral circuitry, such as the keyboard, disc interface and serial port.

THE IO CONTROLLER

All peripheral Input/Output (IO) operations are either performed by, or controlled by, the fourth chip in the ARM chip-set - IOC - which provides an interface between the rest of the ARM chip set and standard peripheral controller chips such as the floppy disc controller and the serial controller. To understand what IOC does, we need to look at the problems of accessing peripheral devices. In general, each peripheral system (floppy disc, hard disc, serial port, etc.) is controlled by an off-the-shelf chip designed for that particular interfacing operation. Unfortunately, as these interface chips are not designed specifically for use with the ARM, they do not dovetail into the system in the same way that MEMC and VIDC do. Furthermore, these devices have to interface with the 'outside world', and as external events can occur at any time, they cannot be guaranteed to be synchronous with the operation of the ARM processor. To overcome this problem, a system has to be adopted by which the operation of the ARM is frozen each time an IO access is made (by holding the $\phi 2$ clock high), until the peripheral device signals that it has completed the access.

A further twist to the story is that as an IO access can last an arbitrarily long time, it must be possible to perform a DMA cycle in the middle of it, as described last month, otherwise effects such as flickering on the screen would be seen. For this reason, the peripheral controllers have to use a separate data bus from the ARM processor, so that an IO operation can continue during a DMA transfer. Latches are used to hold the data for the IO operation. Figure 1 is a block diagram showing the arrangement of IOC.




Figure 1. Highly simplified block diagram of IOC and peripheral circuits

To achieve all this, MEMC asserts a signal called IORQ (IO Request) whenever an access is made to an IO device. MEMC then waits until the IO device asserts another signal, IOGT, to announce that the operation is complete. All this, though, is far too complex for the average peripheral controller chip, and hence IOC performs the necessary operations automatically. However, to do this, IOC has to make assumptions about how fast the peripheral device can perform an operation. To allow



THE WORLD'S MOST POWERFUL MICRO

A3000	£649	410/1	£1199
310	£899	420/1	£1699
310M	£959	440/1	£2499

**SPECIAL OFFER UNTIL JANUARY 1990
BUY AN A3000 OR ACORNS DESKTOP
PUBLISHER AND SAVE 20% OFF THE
COST OF A MORLEY RAM BOARD**



THE A3000 OPTION ACORN FORGOT

- | | |
|---|---|
| ☐ Easy to install simply plug in and run | ☐ Includes full fitting kit and instructions |
| ☐ High quality Japanese Drive | ☐ Dual Drive Kit |

£125

LEADS & MISC. HARDWARE ETC.

Arch Monitor Leads:		Printer Stand 80 col	£15
SCART	£8	Printer Stand 135 col	£19
9 Way 'D' (Msyno)	£8	Tilt & Swivel Monitor Stand	£11
Arch Serial Lead	£8	Monitor Stand/plinth	£11
Arch Printer Lead	£8	BBC	£13
BBC Printer Lead	£8	Master	£14
2 to 1 Printer switch	£20	BBC/Master SCSI	£50
3 to 1 Printer switch	£30	Hard Disc Interface	£18
4 to 1 Printer switch	£36	Eprom Eraser	£18
64k Printer Buffer	£115	Eraser with bmer	£23
256k Printer buffer	£199		

(NOTE switching units & print buffers come with printer lead)

The Morley TELETEXT ADAPTER is now available for the Archimedes. The specification including screen dumps etc., is the same as the BBC version but connection is via a Podule socket.

£125

EXISTING USERS OF OUR BBC TELETEXT ADAPTER WE CAN UPGRADE THE UNIT FOR THE ARCHIMEDES FOR

£35


RING FOR DETAILS

We are now an Acorn dealer and service centre. If you would like to have a look at the A3000 or any other Acorn/Morley products please feel free to call in and discuss your requirements with our staff.

COMING SOON

Morley Module Podule

Allows frequently required 'Modules' to be loaded into a non volatile storage area on the podule. Thus saving the tedium of switching through your discs for the modules required.



THE BEST VALUE MEMORY UPGRADES

- | | |
|---|--|
| ☐ Easy to install simply plug in and run | ☐ 1 Meg upgrade gives you a total of 2 Meg on-board |
| ☐ Fully compatible with all Acorn software including desktop publisher | ☐ 1 Meg board upgradeable to 3 Meg |
| ☐ A must for all serious Archimedes owners | 1 Meg Upgrade |
| ☐ Make full use of Acorn's powerful Desk-Top Publishing package | 3 Meg Upgrade |
| | 1 Meg to 3 Meg |
| | 305 1/2 Meg |
| | 400 Series 1 Meg |
| | 400 Series 3 Meg |

£150

£415

£298

£105

£145

£395

ARCHIMEDES PERIPHERALS

Colour Monitor	£220	300/400 series	
Mono Monitor	£73	Acorn Rom Podule	£56
Printer Lead	£9	2 Slot Backplane	£37
A3000		4 Slot Backplane	£59
Monitor stand	£29	I/O Podule	£80
User port & MIDI Podule	£49	Midi Podule	£65
Serial Upgrade	£19	20 Meg Hard Disc & Controller	£465
Econet Upgrade	£49	Acorn DeskTop Pub.	£149
Pipedream 3	£147	Clares Pro Arisan	£145
Risc Os Companion	£49	Clares Artisan	£29
1st Word +	£69	Clares Toolkit	£34
Autodesk CAD	£79	Clares Toolkit +	£43
Acorn PC Emulator	£99		



Kit includes 5.25" Teac 80 track drive, case, power supply; 3.5" drive cradle, interface and leads

£169

A3000 SCSI PODULE £149

A3000 WINCHESTERS

Including SCSI Podule, drive, case and leads

20 meg	£465	30 meg	£495
40 meg	£575	60-200 meg POA	

TO ORDER ...

CARRIAGE £1 on all orders. £3 on larger items (adapters). VAT-UK customers please add 15% to cost excl. carriage. BY POST: Enclose cheque made payable to MORLEY ELECTRONICS LTD.

BY PHONE: By quoting your ACCESS or VISA card number. Goods usually despatched by return. Government and Education orders welcome.

this, IOC can perform any peripheral access at one of four different speeds. Three of these are *fast*, *medium* and *slow* which simply wait a fixed time after the start of the operation before asserting IOGT. The final access method is called *Sync*, and synchronises the access to a 2MHz clock signal. This method is compatible with many peripheral controller chips designed for connecting to the 6502 micro-processor used in earlier Acorn computers.

IOC also provides a number of internal IO devices. In particular, there is a very simple serial port that is used to transfer data to and from the keyboard. The keyboard itself contains its own processor which is used to control the other end of the serial link and scan the keyboard. IOC also contains a six-bit general purpose IO port which is used for various internal purposes such as muting the internal speaker and monitoring the acknowledge signal from the printer. Some other features of IOC are described later.

THE IO MEMORY MAP

All we have so far looked at are the basics of IO accesses, but not at how the ARM processor actually performs them. In fact, IO devices appear to the processor as memory locations, and are accessed using the STR and LDR instructions. Referring back to the ARM system memory map given in the second article in this series, the 4Mbytes of address space between address &3000000 and &3400000 is allocated to 'Input/Output Controllers'. However, in the Archimedes, only the top half of this is used to access IOC, while the bottom half is left free.

IOC further splits its allocation into four chunks which are identical

except for access speed (Fast, Medium, Slow or Sync). This allows the speed of an access to be determined by the address used for the access. Each chunk is further split into eight blocks, each 64K in length. The first block is used to access registers internal to IOC, while the others are allocated to different peripheral controllers. Figure 2 sums up the situation.

Address	Type	Bank	IC	Use
&3240000	Slow	4	--	Internal Expansion cards
&3270000	Slow	7	--	External Expansion cards
&32C0000	Med	4	--	Internal Expansion cards
&32D0000	Med	5	HD63463	Hard Disc register write
&32D0008	Med	5	HD63463	Hard Disc DMA read
&32D0020	Med	5	HD63463	Hard Disc register read
&32D0028	Med	5	HD63463	Hard Disc DMA write
&3310000	Fast	1	1772	Floppy disc controller
&3340000	Fast	4	--	Internal Expansion cards
&3350010	Fast	5	HC374	Printer Data
&3350018	Fast	5	HC574	Latch A
&3350040	Fast	5	HC574	Latch B
&33A0000	Sync	2	6854	Econet controller
&33B0000	Sync	3	6551	Serial port controller
&33C0000	Sync	4	--	Internal Expansion cards

Figure 2. Addresses of peripheral devices


The *internal expansion* area is where so-called podules are mapped, and *external expansion* is available for extra podules that can be added outside the computer. The IC column indicates the device numbers of the individual peripheral controller chips, and you can find more details of these by referring to the chips' data sheets (available from component suppliers). The type column shows the access speed, while the bank number refers to the block as decoded by IOC. The two latches (Latch A and B) are used to control various features of the floppy disc system, such as which drive to use.

A very important point to note here is the *width* of the data bus used for peripheral devices. Remember that the ARM itself uses 32-bit words, and hence

SILICON VISION

SOFTWARE FOR THE ARCHIMEDES COMPUTER SYSTEM

RoboLOGO



This revolutionary new extension to traditional LOGO, made possible only by the enormous computational power of the Archimedes provides three dimensional control of an articulated humanoid or animal figure through the use of a standard LOGO language. Sophisticated natural commands such as Walking Turning Bowing, and Picking, etc are automatically represented graphically by natural movements of the 3D figure. This natural form of graphical response is readily understood by students using LOGO to learn the concepts of logic & reasoning. The traditional Turtlegraphics & 3D Gridler features are also supported for easy transition to this innovative concept in natural response LOGO.

£69.95 (ARC) New

REALTIME SOLIDS MODELLER

The package includes both the sophisticated design environment of SolidCAD and the high speed capability of a Realtime Graphics Language module to provide the fastest programmable animation facilities bringing any design to life from within your own programs. Facilities include 3D Rotate, Scale, Orbit Perspective, Position & extensive display styles for wireframes hidden-surface removal, smooth shading and multiple light sources with individual intensities.

£89.95 (ARC) New

GATE ARRAY DESIGN SYSTEM

An introductory course for teaching Silicon Chip Design with facilities for Array design, Cell design, On-line Help and a tutorial on integrated circuit design. Ideal as a low cost teaching tool where expensive silicon fabrication facilities are not required.

£89.95 (ARC) New

FILM-MAKER



The package provides an interactive environment to create animated sequences of 3D scenes with dynamic camera motion for walk-throughs and light-paths for objects within the scene. The fully graphical environment requires no programming or textual entry and the capability to calculate smooth shaded frames of complex scenes with lighting effects at rates of 60 minute allows fast interactive design of animated sequences. A large number of these frames can then be stored using built-in compression facilities to play-back at video scan rates for on-screen animation or video recording. Fully compatible with SolidCAD and SolidsRENDER, animation Oscars are now within your reach.

£79.95 (ARC) New

SOLIDCAD

The next generation CAD package combining 2D Draughting and 3D Modelling techniques with advanced smooth shading and lighting effects to provide the ultimate 3D Draughting System for Architectural design, Interior design, Engineering design and Teaching CDT. Allows drawing in plan, front & side elevations and also directly in 3D to visualise a model while it is being created. Powerful zoom, pan, sweep, extrude and macro facilities are also provided to enhance design productivity.


£49.95 (ARC) New

SOLIDTOOLS

The fully integrated environment for 3D CAD, Animation, Rendering & Hardcopy. The package includes SolidCAD, FILM-Maker, SolidsRENDER, Realtime Graphics Language, SuperDump & SuperPlot for a turnkey solution satisfying all your requirements.

£275.00 (ARC) New

ARC-PCB PROFESSIONAL



The ultimate PCB design package developed specifically for the Archimedes is now even better. ARC-PCB Professional follows on the success of the original and provides Faster & Improved Automatic Routing, Oval & Circular pads with fully variable sizes, Faster Redraw, Extended library part manipulation, & Instant Editing operations for substantially increased productivity. This Professional version operates orders of magnitude faster than the original and surpasses all other PC-based PCB design systems in features & speed of operation for the fastest turnaround from concept to finished board design. Take the lead for your PCB designs before your competitors do.

£375.00 (ARC) New

SOLIDSRENDER

The fastest most advanced Ray Tracing package for the Archimedes producing photo-realistic images of SolidCAD designs or FILM-Maker animations which take into account light sources, reflections, shadows, transparencies, refractions and textures for the highest quality pictures from the leading 3D graphics experts renowned for technical excellence.

£79.95 (ARC) New

RiscBASIC

The best BASIC V compiler money can buy. Here's what the reviewers say: "If you are looking for THE compiler to go for, and are confused about which one deserves to win the very public battle that has been raging in the advertisements, well my preference is for RiscBASIC" - RISC USER Aug 1989. "In summary, BASIC V is the best version of BASIC produced and RiscBASIC provides the most compatible, fastest compiler for this language. My congratulations to Silicon Vision" - Archive June 1989. "very useful indeed for development work...produced significantly more efficient code" - Micro User July 1989.

£99.95 (ARC) New

All Archimedes software run in native mode on A305-A440 & A3000 with Arthur 1.2 or RISC OS

**SILICON VISION LTD, SIGNAL HOUSE, LYON ROAD, HARROW
MIDDLESEX HA1 2AG. TEL: 01-422 2274 or 01-861 2173
FAX: 01-427 5169. TELEX: 918266 SIGNAL G.**

**ⓧ (Access/Mastercard/Eurocard/American Express accepted)
All prices include VAT and Carriage (Overseas orders should add £4)**

the addresses of two adjacent words in memory differ by a value of four (because the address is always specified in terms of eight-bit bytes). Processors that use 32-bit data buses are all relatively new, and almost all the available IO controllers work with either eight or sixteen-bit buses. Indeed, IOC limits devices to using an eight or sixteen bit bus. On the Archimedes, the HD63463 Hard Disc Controller is a sixteen-bit device, while all the others use eight bits.

A final point to make is that all of the IOC address space is protected against being accessed when the processor is in user mode. Therefore all accesses to IO devices must either be made from interrupt code or within a module, unless a short program is used to enter supervisor mode prior to the transfer.

INTERRUPTS

Imagine what has to happen when a program is running, and the user presses a key on the keyboard. This keypress is passed back to IOC, and in some way the operating system must take note of it. However, because a program is running, the operating system cannot look at IOC constantly to catch each keypress. Instead, a technique known as an *interrupt* is used. What happens is that when a key-press is received by IOC, it sends a signal known as an interrupt request (IRQ) to the ARM processor. On receipt of the IRQ signal, the operating system suspends execution of the program (after completing the current instruction) and jumps to a routine to read the key press and store it for later. When this has been done, execution of the original program is resumed. The entire interrupt process takes only a few microseconds, and the main program is oblivious to the fact that the interrupt has occurred.

Interrupts constitute a very powerful technique when the operating system is

required to respond to events which happen asynchronously with any program being executed. As this applies to most IO operations, IOC makes extensive use of interrupts.

There is a second level of interrupt known as the Fast Interrupt (FIQ). These are similar to the normal IRQs, but are guaranteed a quicker response from the ARM processor. For this reason, FIQs are only used when speed is of the utmost importance. For example, for data transfers by the floppy disc controller and Econet interface.

Whenever an IRQ or FIQ occurs, IOC keeps a note of the source of the interrupt. When the ARM processor responds to the interrupt, RISC OS can interrogate IOC to find out the source and act accordingly.

TIMERS

Contained within IOC itself are four timers, which are basically counters that can be loaded with a particular value, and then decremented at a constant rate. Each time a timer is decremented through zero, it generates an interrupt. Of these timers, two have dedicated hardware uses - one generates the baud rate clock for the serial link to the keyboard, and the second is used to generate the receive baud rate for the serial port when using split speeds. This is necessary as the serial interface chip can only generate a single baud rate internally. A third timer is used by RISC OS to generate an interrupt every hundredth of a second. This is used to control tasks such as keyboard auto-repeat, as well as updating the value of the pseudo-variable TIME. The final timer is free for the user's own program.

THE IIC BUS

A final method of accessing peripheral devices employed on the

continued on page 61

- Full feature word processing • Full capability DTP • Multiple documents in memory • Multiple windows on each document • Any scale view from 196-900%
- Automatic hyphenation • Built-in spelling checker • Spell check as-you-type • Full 24-bit RGB, CMYK & HSV colour control • Fast character mode printing • 300K free workspace on a 1Mbyte machine • Supplied with 13 outline fonts
- Flowing graphics with text • Automatic index generation • Automatic contents generation • Automatic abbreviation expansion • Automatic file conversion from other WPs • Virtual memory system - unlimited document size
- Simple to use - only 5 main menus • Word count • Scaled printing • portrait & landscape pages in one document • active master pages • thumbnail printing • rotated printing • left/right only printing • pamphlet printing • collated printing • pause between pages • cut/copy/paste between documents • multiple master pages • fully customisable start-up • programmable key short cuts • overlaying styles • styles can be applied to any part of a paragraph • dynamic memory usage • search & replace for styles and codes • search & replace with wildcards • case-sensitive search & replace • auto-page numbering • roman numbering option • page numbering start at any value • multi-line headers & footers • graphics in headers and footers • graphics on/off options for screen & print • style merge from other documents • style template documents • condensed & expanded text • left, centre, right and decimal tabs • each style can have its own ruler • single & double underline options • text strikethrough • underline colour control • rule-offs • hyphenation control on individual words • hyphenation exception dictionaries • programmable tab leader characters • internal accuracy to 1/72,000ths inch • horizontal and vertical kerning to 1/1000ths em • text flow around frame control (both sides, either side or neither side) • guide frames • controllable frame snap • embedded graphics frames in text • embedded graphics on the line • go to page & chapter • two guess-misspell-word options • word anagram solutions • crossword solving facilities • 8 user dictionaries • auto-load user dictionaries on start-up • user dictionaries compatible with Spellmaster • all measurements can be specified as inches, millimetres, centimetres, meters, points, feet, yards or picas • abbreviation expansion as you type • word substitution as you type • insert current date & time options • controllable preferences for measurement units & default scale views • character mode printer drivers for Epson & Laserjet printers •

IMPRESSION

*If other programs can offer all these features,
then they might be as good as Impression.*



Computer Concepts Ltd

Gaddesden Place
Hemel Hempstead
Herts HP2 6EX
Tel. 0442 63933

Hints & Tips. . . Hints & Tips

PRINTER DRIVERS AND Alias\$@PrintType

Lee Calcraft

When a file is dragged to a printer driver, exactly what happens depends on the file type of the dragged file. The driver software first checks the printer aliases to see if there is an alias for the particular file type - for example:

```
Alias$@PrintType_FF9
```

You can display these by typing *SHOW. But note that none is set by default.

Printer aliases usually take the form: Alias\$@LoadType_nnn<application> -print where nnn is the file type, and <application> is the application name (together with directory path).

If the printer driver finds the required print type, it will run the nominated application (loading it if it is not already installed), and request that it prints the file. The application will then typically dialogue with the driver to print the file. In the case of a sprite for example (i.e. type FF9), dragging a sprite icon to a printer driver will cause Paint to be loaded, and routines from Paint will then be used to print out the sprite by making calls to the printer driver.

Printer aliases are usually set up in the !Boot files of an application, so that they are known to the system as soon as a directory viewer containing the application is opened. But if no alias is found for a particular file type, the user receives the message: "I don't know how to print Sprite files; do you want me to print your file as plain text?". The exception to this is files of type ASCII (FFF), which are printed as a straight text file.

SYNTAX ERRORS FROM SYSTEM FONTS

Lee Calcraft

If you install a new system font which uses the same shaped character for an "O" as for a zero (or if you just redefine the zero

character to match the "O"), you will get syntax errors if you use cursor editing on a Basic program. This occurs because in cursor editing, Basic reads characters directly from the screen, and will read both zeros and "O"s as zeros, though you will not realise this until you re-run your program. In those circumstances, copying:

```
FOR A=1 TO 10
```

will give you

```
FOR A=1 TO 10
```

PRINTING THE LAST LINE

Alan Wrigley

Printers are strange creatures sometimes and one little quirk that fools some people is that a line of print will not be printed unless it is followed by a linefeed or carriage return, or the printer is taken off-line. This can result in graphics dumps, for example, appearing to ignore the last line. If this happens, simply press the button which takes the printer off-line, and hey presto, the last line will be printed.

RETURN TO DESKTOP

Alan Wrigley

If you have used F12 from the Desktop in order to access the command line interpreter, it may not be immediately obvious how to return to the Desktop. You might think that typing *Desktop will do the trick, but in fact all you will get is a blank window on the screen. The correct way to return is simply to press Return at the * prompt, which will drop you back into the Desktop.

IF-THEN

C. J. Hayes

Into the Arc (Volume 2 Issue 9) stated that it is a matter of personal preference whether to include the THEN statement in an IF-THEN construct. There is, however, one circumstance in which it must be included, and that is when a star command follows immediately after. For example, the line

```
IF X=10 *FX3
```

Hints & Tips. . . Hints & Tips

would generate an error because the Basic interpreter would confuse the star command with a multiplication symbol, and search for a variable called FX3.

PRINT TAB

Alan Wrigley

If you specify only one parameter in a TAB statement, e.g. PRINT TAB(10), the data which follows will be printed starting at column 10 of the line that the cursor is currently on, unless the cursor is already beyond that position, in which case it will move to column 10 of the next line. The result is exactly the same if you are sending the data to a printer.

However, using two parameters, e.g. PRINT TAB(20,15), defines a specific position on the screen, i.e. line 15 column 20. The cursor will move to this position irrespective of where it was previously, but with a printer this will simply be ignored, as the print head cannot move up and down at random.

This is all fine if you know exactly where on the screen the output is to appear. But what if you don't know where the cursor is at present but you want to move it to a particular position on, say, the previous line? A simple way to do this is to determine the current line with VPOS, and use this as the basis for the parameters, e.g. PRINT TAB(20,VPOS-1).

DISC FORMATS

Tom Johnson

If you back up a D format disc onto an E format one, the backup disc reverts to D format. As a result, if you have a number of old D format discs and wish to convert them to E format it is a laborious task to transfer them all directory by directory if you only have a single drive. A quicker method is to use the Fast Directory Copier (RISC User Volume 1 Issue 6) to copy the root directory, together with all its sub-directories, onto a newly E formatted disc. This is a little slower than backing up but a lot faster than copying individual files and directories using a single drive.

RU

Under the Lid (continued from page 57)


Archimedes is a system known as the IIC bus (read "I squared C"). This is a specialised bus that was developed by Philips, and is unusual in that it is a serial bus. This means that data is transferred bit by bit, rather than byte by byte or word by word, therefore making the bus relatively slow. However, the IIC bus has the advantage that far fewer lines are needed. In fact, only two connections are used - the serial data itself (labelled SDA) and a clock to synchronise the transfers (SCL). These lines are connected to two bits of the general purpose port on IOC.

Because of its lack of speed, the IIC bus has limited use, and is only used to

communicate with the real-time clock and CMOS RAM chip. However, the SDA and SCL signals are also made available to podules, and can be used by them. It is also relatively complicated to control the bus, because of the complex timings needed between the two signals. Luckily, though, RISC OS provides the SWI call "IIC_Control" to do the job for you.

That brings us to the end of this series, and I hope that it has been interesting. Unfortunately, it is such a vast subject that we have only been able to scratch the surface, but I hope that it has provided an overview of what is happening within the Archimedes.

RU




16 BIT SCSI

Winchesters and controller card for 300/400/A3000. Exceptionally fast. Up to 7 devices per card. Internal drives come with all necessary mounting hardware. External drives have their own PSU and fan. Please specify if for A3000.

<i>Internal (inc. card)</i>	<i>External (inc. card)</i>
20Mb £375.00	20Mb £535.00
45Mb £495.00	45Mb £655.00
70Mb £895.00	70Mb £1055.00
135Mb £1595.00	90Mb £1249.00
180Mb £2065.00	135Mb £1625.00
Card only £199.00	170Mb £1850.00
A3000 Card £199.00	330Mb £2845.00
<i>BBC Winchesters available from £359.00</i>	
<i>p&p £15.00 winchesters, £8.00 card only</i>	



**Oak Computers, Cross Park House,
Low Green, Rawdon, Leeds LS19 6HA
Tel: 0532 502615 Fax: 0532 506868
Also available from all good Acorn Dealers**



Output may be scaled and sent to ports, network or file.

£29.95 (p&p £4.50)

Worra Plotter

*HPGL plotter driver
to allow Drawfiles to be
plotted to HPGL plotters.*

Worro *Computer S*


All prices exclude VAT

PDT

**Parametric
Design Tool.
Professional
Computer**

Aided Design. 2D parametric design and modelling system allows designs to be tested, animated and easily modified before being output to an HPGL compatible plotter or via DXF files to other CAD systems or !Draw and then on to DTP etc.

£359.00 p&p £6.00



TAPE STREAMERS




Available from mid-December, Oak SCSI Tape Streamers provide the ideal means of backing up data from SCSI or ST506 winchesters, networks or indeed any filing system. Desktop software allows files for backing up to be easily specified, and data can be saved and restored on a file by file basis. Add £100 if you do not have a SCSI card.

60Mb (per tape) £999.95
150Mb (per tape) £1254.00

Worra Battle

Classic Tank Battle Game. Voted best game at the Personal Computer Show by the

high speed vector graphics.



£14.95 (p&p £4.50)



NOT A COMPETITION

This is NOT a competition entry, but you might be interested in the expression:

$$\frac{\text{LOG} \left(\frac{\text{LOG}(4)}{\text{LOG}(\sqrt{\dots\sqrt{4}})} \right)}{\text{LOG} \left(\frac{\text{LOG}(4)}{\text{LOG}(\sqrt{4})} \right)}$$

It evaluates to an integer equal in value to the number of square root signs on the second (of the four) lines, including zero (though limited to 30 by the accuracy of Basic V). The four fours may be replaced by four of any positive number, except 1, not necessarily integers.

C.R.J.Singleton

THE GREAT PRINTER CONSPIRACY

Why is it that reviewers and other writers in your magazine are obsessed with 24-pin impact dot-matrix and laser printers? 24-pin printers are very nice, but not so good for DTP applications, and the notion that you can rush out and buy laser printers is laughable. You seem to be ignoring a type of printer which falls neatly inbetween.

I refer to the inkjet dot-matrix printers, which seem to have been complete ignored apart from the slow colour-only Integrex 132, and that has been around for five years or so.

I use a Hewlett-Packard DeskJet-Plus, available from various dealers, for which I paid £499 plus VAT. You get a printer with 300 dpi resolution, which produces quality very close to that of a laser printer with ordinary cheap typing paper. And Hewlett-Packard throw in a year's next-day-response on-site maintenance as part of the warranty. The LaserJet printer driver supplied by Acorn works fine with the DeskJet.

So please, let's have a review of this versatile printer very soon.

Richard Sterry

As we hinted in last month's article *On Printers, Drivers and Fonts*, we will be taking a look at the DeskJet in a forthcoming

issue. As Mr. Sterry notes, it appears to represent an excellent low cost alternative to the laser printer.

RISC USER SPECIAL DISC AND RISC OS

Now that I have the new RISC OS system fitted to my Arc, I find that the RISC User Volume One Special Disc does not function. Can you please advise me?

Ernest Swift

The RISC User Volume One Special Disc was released on the first anniversary of the launch of RISC User. It contained the first version of ArcScan with the index for volume one of RISC User, a number of utilities, and a highly effective visual demonstration. The Special Disc will work under RISC OS, but must be started by pressing Shift-Break as it is not designed to be run from the Desktop. The only possible sources of errors are inappropriate configuration settings, particularly with regard to ScreenSize and SpriteSize. If these are adjusted (with the Task Manager) to 160K and 16K respectively then all should be well.

The disc itself is no longer available, having been superseded (partly) by ArcScan II and the RISC User Toolbox. These products both provide superior and extended versions of the relevant software.

FOR SOME THE WEEK STARTS ON SUNDAY

What changes should be made to your RISC User Desktop Diary to display the calendar with the days in the order SMTWTFS, instead of the MTWTFSS order as listed?

Nobilangelo Ceramalus

The changes needed are as follows. Modify the two lines from part one shown below:

```
2270 ... -2+D%)MOD7
to: ... -1+D%)MOD7
3440 ... "Mon Tue ... Sun"
to: ... "Sun Mon ... Sat"
```

and in part two of the program:

```
3340 day$( )="Monday", ... ,"Sunday"
to: day$( )="Sunday", ... ,"Saturday"
```

RU

The RISC USER Archimedes Toolbox

A Powerful Utility for the ARCHIMEDES offering:

Memory Search - a full screen editor which enables you to find a sequence of bytes, words or characters quickly and easily.


Memory Editor - with the help of this you can examine and alter memory in either hex or ASCII mode.

Disc Sector Editor - a most helpful command for examining and changing disc contents directly. Ideal for repairing corrupted discs and recovering lost files.

Dissassembler - this command displays the contents of memory as ARM instructions including floating point and co-processor mnemonics.


Plus many other powerful commands including:

- File Find
- File Compare
- File Go To
- Exall
- Catall
- Memory Dump



The full Screen Disc Sector Editor

Archimedes Movie Maker



A Full-feature Application for Creating Cartoons and Animated Sequences:

- Fully mouse controlled
 - Sprite import-export
 - Variable frame rate
 - Multi-size brush
 - 256 colour palette
 - Sprite brush
- and many other features

Please rush me my:

Archimedes TOOLBOX disc and documentation Code 1401A

members' price of £5.75 ☐

non-members' price of £15.00 ☐

Movie Maker disc and documentation Code 1410A

members' price of £4.75 ☐

non-members' price of £15.00 ☐

Name _____

Address _____

Membership No _____

Price £ _____

Postage (60p per item) £ _____

Total £ _____

I enclose a cheque for £ _____ OR please debit my Access, Visa or Connect account, Card

No _____ / _____ / _____ Expiry _____ / _____ Signed _____

Send to: BEEBUG Ltd, 117 Hatfield Road, St Albans, Herts AL1 4JS. Telephone (0727) 40303

Technical Queries

Dear Sir,

With regard to memory allocation under RISC OS, I find that some programs lock away memory in the module area, and the only way I have found to get it back is to do a hard reset. Examination of the area using *ROMModules does not show any difference, yet a block of memory has been gobbled up and not returned when the application has been removed. Where has the memory gone, and can you get it back without a hard reset?

Also on memory, I have tried to get the MemAlloc program working, but as yet I have not been successful. How do you do it?

Peter Foster

The memory which has been 'lost' in the RMA (relocatable module area) has not been taken by any application but by any modules required by the application (e.g. the floating point emulator). These modules are not removed when the application terminates. In order to recover any memory lost in this way, type:

*RMCLEAR

at the command line (the star prompt) to kill off all relocatable modules in RAM. Then activate the Task Manager and drag the *Module Area* bar to the left to reduce the memory allocation. However, do NOT do this if there are any applications installed. If necessary, the alternative command *RMKill <module name> can be used to remove individual modules by name. Incidentally, the *ROMModules command will not list any modules which are in the RMA; it only lists those in ROM. Use instead the *Modules command.

As for the MemAlloc module (first described in RISC User Volume 2 Issue 8 p59), once it has been loaded then the sizes of various memory areas can be changed using star commands. For example, type:

*ScreenSize 160

would set the screen size to 160K. For more details type:

*Help MemAlloc

once the module has been loaded.

Mike Williams

Dear Sir,

I have a multi-sync monitor. When I change to high resolution modes the width of the image shrinks about 15% (from the right). How can I preserve the 'normal', i.e. mode 12, aspect ratio across all modes?

Nobilangelo Ceramalus

There are two points at issue here. As far as shrinkage of picture image is concerned, this is a function of the monitor being used. The Taxan 770 multi-sync monitor, which is recommended for use with the Archimedes, has a number of pre-set controls which can be adjusted to ensure that the picture fully fits the screen in the multi-sync modes. Other makes of monitor may or may not provide for such adjustments.

Secondly, in any of the multi-sync modes (modes 18 to 21) the screen displays 64 rows of 80 characters each, instead of the 32 lines of 80 characters in mode 12, for example. Thus it is impossible to preserve the aspect ratio as far as text is concerned. However, for graphics the screen area is always addressed as 1280 points horizontally by 1024 points vertically (except modes 16, 17 and 24) and thus the aspect ratio remains constant across all except these modes, but the number of colours and screen resolution changes. For example, mode 12 provides 16 colours with a graphics resolution of 640 by 256, while mode 20 (a multi-sync mode) provides a resolution of 640 by 512 also in 16 colours. In the multi-sync mode the higher resolution leads to a better quality screen image, which in turn permits the use of twice the normal number of rows of text.

Mike Williams RU

RISC USER MEMBERSHIP

RISC User is available only on subscription at the rates shown below. Full subscribers to RISC User may also take out a reduced rate subscription to BEEBUG (the magazine for the BBC micro and Master series).

<i>Subscription Rates</i>	<i>RISC User</i>	<i>RISC User & BEEBUG</i>	All subscriptions, including overseas, should be in pounds sterling. We will also accept payment by Connect, Access and Visa, and official UK orders are welcome.
UK, BFPO, Ch.Is	£16.90	£25.00	
Rest of Europe & Eire	£24.00	£36.00	
Middle East	£29.00	£43.00	
Americas & Africa	£31.00	£46.00	
Elsewhere	£34.00	£51.00	

Back Issues

We intend to maintain stocks of back issues. New subscribers can therefore obtain earlier copies to provide a complete set from Vol.1 Issue 1. Back issues cost £1.20 each. You should also include postage as shown:

<i>Post and Packing</i>	<i>UK, BFPO, Ch.Is</i>	<i>Europe plus Eire</i>	<i>Elsewhere</i>
First Issue	60p	£1.00	£2.00
Each subsequent Issue	30p	50p	£1.00

MAGAZINE DISC

The programs from each issue of RISC User, together with a number of additional items, are included on a monthly 3.5" disc. This will be available to order, or you may take out a subscription to ensure that the disc arrives at the same time as the magazine.

<i>Disc Subscription Rates</i>	<i>UK</i>	<i>Overseas</i>	Disc subscriptions include postage, but you should add the appropriate rate (see above) per disc for individual orders.
Single issue discs	£ 4.75	£ 4.75	
Six months subscription	£25.50	£30.00	
Twelve months subscription	£50.00	£56.00	

RISC User & BEEBUG, 117 Hatfield Road, St Albans, Herts AL1 4JS.
Tel. St Albans (0727) 40303 FAX. (0727) 60263

(24hrs answerphone for Connect/Access/Visa orders and subscriptions)

RISC USER MAGAZINE DISC CONTENTS

System Fonts


You can change the look of your screen by using any of the ten System Fonts provided on this disc.

A Voice Module Generator

Use the mouse to create designer waveforms, and automatically generate voice modules from them.

Keystrip Generator

A new enhanced utility for generating your own keystrips.



Coloured Text Panels

A module for creating three dimensional coloured slabs for text displays.

A Check Save Module

A short utility which prevents you from overwriting files by offering a prompt if a filename already exists.



Pontoon

An Archimedes Desktop version of this very popular card game.

Programmer's Reference Manual

The contents of three pages which were omitted from the Programmer's Reference Manual.

ArcScan Data

This month's ArcScan data files.


Plus the following programs
from RISC User magazine:

Setting Filetypes

A very useful utility which allows you to set the filetype of files directly from the Desktop.

Mastering the Wimp (Part 5)

A program illustrating the problems connected with the creation of windows for displaying text.



THE INDISPENSIBLE PACKAGE FOR ALL HARD DISC USERS

Beebug Hard Disc Companion

This package contains three comprehensive, easy to use utilities to backup your hard disc, create file archives, and search for files.

All three utilities were written specifically for the RISC OS desktop environment, and are multi-tasking.

Hard Disc Backup

The backup facility allows you to save the contents of your hard disc onto floppy discs. It is comprehensive, easy to use and very reliable. Two types of backup are possible; Full and Incremental. Full saves every file on the hard disc to floppy. Incremental saves only those files added or changed since the last backup. Certain files are automatically compressed to reduce the number of floppies needed for the backup. Restore is equally comprehensive with options for full, partial or file by file restore. Individual files can be restored by dragging from the backup disc to the required destination. An automatic reminder facility can be set up to remind you at regular intervals to perform a backup.


Members price:

£35.00

Stock code: 0106C

Econet Compatibility

Although designed for hard disc users, this package is ideal for use with Econet. Site licences are available - please phone for details.



Spark - File Archiver

Spark is an archiving program used to create and maintain file archives. It is entirely WIMP based, with the contents of an archive displayed in a similar way to an ADFS directory. Files may be dragged directly from a directory into the archive, or vice versa. An important feature of **Spark** is that it automatically compresses the files being archived. **Spark** is very easy to use, and has many uses. For example, you could put 2MB (or more!) of sprites onto an 800K floppy disc. Then, to load a sprite into ArcPaint, simply drag it from the archive - it will be decompressed automatically. **Spark** has many powerful features, and is compatible with the public domain archiver, **Arc**.

Find File

Find File is a fast, easy-to-use utility for locating files on hard disc, floppy disc and Econet. **Find File** runs from the multi-tasking Desktop environment, so it can be left to search for a file while you do other things. As well as finding individual files, **Find File** can locate files that match a wildcarded search string, or that have a specified filetype. Once a file has been located, **Find File** can give full information about a file including its filetype, length, and pathname. In addition, you can open a directory viewer on the file so that it can be easily loaded, executed, deleted etc.